

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY QUANTITIES	LIGHTING QUANTITIES
				STE 80/20	STE 50/50
25000110	SEEDING, CLASS 1A	ACRE	0.25	0.25	
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	155	155	
* 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5	
* 42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	12	12	
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	347	347	
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,618	7,618	
* 42400800	DETECTABLE WARNINGS	SQ FT	151	151	
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	368	368	
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	886	886	
* 44000600	SIDEWALK REMOVAL	SQ FT	6,615	6,615	
* 44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	6	6	
* 44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	8	8	
* 60600605	CONCRETE CURB, TYPE B	FOOT	18	18	
67100100	MOBILIZATION	L SUM	1	1	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	487	487	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	282	282	
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3,100		3,100
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	8,700		8,700
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	19,500		19,500
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	4,100		4,100
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	7,900		7,900
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	4,200		4,200
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1		1
* X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	921	921	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X8140105	HANDHOLE (SPECIAL)	EACH	38		38
X8360310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	140		140
XX007393	DECORATIVE LIGHT TYPE A	EACH	56		56
XX007394	DECORATIVE LIGHT TYPE B	EACH	20		20
X8040102	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1		1

* DENOTES SPECIALTY ITEM

208 East Main Street, Suite 100
 Bellville, Illinois 62220
 618.233.5977 phone
 618.233.5977 fax
 www.kaskaskia.com

Kaskaskia
 Engineering Group, LLC

PROFESSIONAL REGISTRATIONS
 Illinois Professional Design Firm
 Professional Engineering Group

LICENSE NO.
 184-004773
 20-5080386

PREPARED BY:

SUMMARY OF QUANTITIES

PROJECT TITLE:
 SEC 10-00085-01-LS
 NORTH MAIN STREET STREETSCAPE
 CITY OF EDWARDSVILLE, ILLINOIS

DESIGNED BY:	LDC	SHEET
DRAWN BY:	SMS	3
CHECKED BY:	GEB	
DATE OF PRE-FINAL:	8/17/12	
DATE OF FINAL:	10/12/12	
SHEET NO. 3 OF 12 SHEETS		
PROJECT NUMBER 09-1074.01		