URBAN

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | | 80% FED 20% STATE 0005 | | | | | |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 10 | 10 | | | | | |
| | | | | | | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 204 | 204 | | | | | |
| | | | | | | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 2158 | 2158 | | | | | |
| | | | | | | | | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | |
| | | | | | | | | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | |
| | | | | | | | | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 36 | 36 | | | | | |
| | | | | | | | | | |
| 25003115 | INTERSEEDING, CLASS 1B | ACRE | 3.35 | 3.35 | 2 | | | | |
| | | | | | | | | | |
| 25003210 | INTERSEEDING, CLASS 2A | ACRE | 2.73 | 2.73 | | | | | |
| | | | | | | | | | |
| 25003310 | INTERSEEDING, CLASS 4 | ACRE | 0.17 | 0.17 | | | | | |
| | | | | | | | | | |
| 25100127 | MULCH, METHOD 3A | ACRE | 1.62 | 1.62 | | | | | |
| | | | | | | | | | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 2158 | 2158 | | | | | |
| | | | | | | | | | |
| 25200200 | SUPPLEMENTAL WATERING | UNIT | 66 | 66 | | | | | |
| 31101180 | SUBBASE GRANULAR MATERIAL TYPE B 2" | SQ YD | 86 | 86 | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND | TON | 353.7 | 353.7 | | | | | |
| | FLANGEWAYS | | | | | | | | |
| | | | | | | | | | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE | TON | 8930 | 8930 | | | | | |
| | METHOD), IL-4.75, N50 | | | | | | | | |
| | | | | | | | | | |
| | *SPECIALTY ITEMS | | | | | | | | |

URBAN

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | | 80% FED 20% STATE 0005 | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT | SQ YD | 1362 | 1362 | | | | | |
| | JOINT | | | | | | | | |
| | | | | | | | | | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE | SQ YD | 3255 | 3255 | | | | | |
| | REMOVAL - BUTT JOINT | | | | | | | | |
| | | | | | | | | | |
| 40800029 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 143443 | 143443 | | | | | |
| | | | | | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 4639 | 4639 | | | | | |
| | | | | | | | | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY | SQ YD | 190 | 190 | | | | | |
| | PAVEMENT, 8 INCH | | | | | | | | |
| | | | | | | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 | SQ FT | 17482 | 17482 | | | | | |
| | INCH | | | | | | | | |
| | | | | | | | | | |
| * 42400800 | DETECTABLE WARNINGS | SQ FT | 1800 | 1800 | | | | | |
| | | | | | | | | | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 | SQ YD | 165931 | 165931 | | | | | |
| | 1/2" | | | | | | | | |
| | | | | | | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 192 | 192 | | | | | |
| | | | | | | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 18657 | 18657 | | | | | |
| | | | | | | | | | |
| 44003510 | MEDIAN REMOVAL PARTIAL DEPTH | SQ FT | 6289 | 6289 | | | | | |
| | | | | | | | | | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 10 | 10 | | | | | |
| | | | | | | | | | |
| 44201765 | CLASS D PATCHES, TYPE II, 10 INCH | SQ YD | 1048 | 1048 | | | | | |

MODEL: Default
FILE NAME: pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 1\Projects\D130718\CADData\Design\D130718-sht-SQQ.dgn

| | | | |
|---|---|---|---|
| FILE NAME = pw:\\IL084EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 1\Projects\D130718\CADData\Design\D130718-sht-SQQ.dgn | USER NAME = kalarm1 | DESIGNED = | REVISED = |
| | | DRAWN = | REVISED = |
| | PLOT SCALE = 100.0000 ' / in. | CHECKED = | REVISED = |
| | PLOT DATE = 12/12/2018 | DATE = | REVISED = |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 171 DES PLAINES RIVER RD. TO S/O 43rd ST.

SCALE: | SHEET OF SHEETS | STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 372 | 2018-016-RS&SW-1 | COOK | 142 | 3 |
| | | CONTRACT NO. 62G47 | | |

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

2 REV. 2/28/19 REV. 1/31/19 REV 1/9/19