

TEMPORARY PAVEMENT MARKING - LINE 5"

FROM STATION	TO STATION	LT/RT	FOOT
STAGE 1			
270+88.33	297+12.64	RT	2,582.68
270+88.33	285+88.82	RT	368.94
270+88.33	297+12.64	RT	2,596.53
283+65.60	298+60.80	LT	1,508.05
283+65.60	298+60.80	LT	1,505.55
283+65.60	298+60.80	LT	1,503.07
285+88.82	297+12.64	RT	1,113.49
339+06.44	353+82.07	LT	1,113.49
339+06.44	353+82.07	LT	1,478.78
340+25.33	342+50.77	LT	56.35
342+50.77	353+82.07	LT	1,139.67
STAGE 2			
268+42.88	298+28.50	RT	2,954.04
268+43.20	283+43.96	RT	371.07
268+43.34	298+28.37	RT	2,967.16
283+43.96	298+28.43	RT	1,476.64
286+36.54	338+04.02	LT	5,232.71
286+36.57	294+10.35	LT	778.80
340+75.04	342+02.51	LT	31.87
342+01.76	351+77.84	LT	978.35
342+02.51	366+77.84	LT	2,501.55
CLEAR LAKE AVE/COOK ST TOTAL			15,702
ROUNDED TOTAL			47,961

MODIFIED URETHANE PAVEMENT MARKING-LINE 5"

FROM STATION	TO STATION	LT/RT	FOOT
268+42.89	298+28.50	RT	2,985.61
268+42.89	298+28.50	RT	2,985.61
268+42.89	298+28.50	RT	746.40
283+65.60	298+60.80	LT	1,495.20
283+65.60	298+60.80	LT	1,495.20
283+65.60	298+60.80	LT	373.80
298+60.80	339+06.44	LT	1,011.41
339+06.44	353+82.07	LT	1,475.63
339+06.44	353+82.07	LT	368.91
340+74.15	343+66.14	LT	73.00
343+66.14	353+82.07	LT	1,015.93
353+82.07	366+77.84	LT	1,295.77
353+82.07	366+77.84	LT	323.94
ROUNDED TOTAL			15,647

TEMPORARY PAVEMENT MARKING - LINE 8"

FROM STATION	TO STATION	LT/RT	FOOT
STAGE 1			
337+97.48	340+25.33	LT	223.03
337+98.25	342+50.77	LT	446.79
339+06.44	340+25.33	LT	116.55
STAGE 2			
338+05.27	340+75.04	LT	266.36
338+05.27	340+75.04	LT	271.02
338+05.27	342+02.16	LT	392.83
ROUNDED TOTAL			1,717

MODIFIED URETHANE PAVEMENT MARKING-LINE 8"

FROM STATION	TO STATION	LT/RT	FOOT
337+97.48	340+74.15	LT	276.67
337+98.25	343+66.14	LT	567.89
339+06.44	340+74.15	LT	167.71
ROUNDED TOTAL			1,013

TEMPORARY INFORMATION SIGNING

DESCRIPTION	LT/RT	HEIGHT	WIDTH	SQ FT
W4-1B	RT	4.00	4.00	16.00
W4-1B	RT	4.00	4.00	16.00
W4-1B	RT	4.00	4.00	16.00
W4-1B	RT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1B	LT	4.00	4.00	16.00
W4-1R	LT	4.00	4.00	16.00
W4-1R	LT	4.00	4.00	16.00
W4-1L	LT	4.00	4.00	16.00
W4-1L	LT	4.00	4.00	16.00
W4-1R	LT	4.00	4.00	16.00
W4-1L	LT	4.00	4.00	16.00
ROUNDED TOTAL				272

REPLACEMENT REFLECTOR

FROM STATION	TO STATION	LT/RT	EACH
268+42.89	298+28.50	RT	38
283+65.60	366+77.84	LT	104
337+97.48	340+74.15	LT	7
337+98.25	343+66.14	LT	29
339+06.44	340+74.15	LT	5
CLEAR LAKE AVE/COOK ST TOTAL			40
TOTAL			223

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL

FROM STATION	TO STATION	LT/RT	EACH
268+42.89	298+28.50	RT	38
283+65.60	366+77.84	LT	104
337+97.48	340+74.15	LT	7
337+98.25	343+66.14	LT	29
339+06.44	340+74.15	LT	5
CLEAR LAKE AVE/COOK ST TOTAL			40
TOTAL			223

GUARDRAIL REMOVAL

FROM STATION*	TO STATION*	LT/RT	FOOT
44+53.98	48+38.98	RT	385.00
46+44.17	48+34.79	RT	190.62
48+26.69	48+54.10	LT	27.41
51+25.63	52+66.45	RT	140.82
51+35.80	51+62.93	RT	27.13
51+35.80	55+59.23	LT	423.43
51+45.86	53+75.62	LT	229.76
CLEAR LAKE AVE/COOK ST TOTAL			1,424.17
ROUNDED TOTAL			1,425

*STATIONS MEASURED ALONG CENTERLINE OF I-72

PAVEMENT MARKING REMOVAL - GRINDING

FROM STATION	TO STATION	LT/RT	WIDTH (IN.)	SQ FT
EXISTING PAVEMENT MARKINGS				
268+42.89	298+28.50	RT	5	1,244.00
268+42.89	298+28.50	RT	5	1,244.00
268+42.89	298+28.50	RT	5	311.00
283+65.60	298+60.80	LT	5	623.00
283+65.60	298+60.80	LT	5	623.00
283+65.60	298+60.80	LT	5	155.75
298+60.80	339+06.44	LT	5	421.42
337+97.48	340+74.15	LT	8	184.45
337+98.25	343+66.14	LT	8	378.59
339+06.44	340+74.15	LT	8	111.81
339+06.44	353+82.07	LT	5	614.85
339+06.44	353+82.07	LT	5	153.71
340+74.15	343+66.14	LT	5	30.42
343+66.14	353+82.07	LT	5	423.30
353+82.07	366+77.84	LT	5	539.90
353+82.07	366+77.84	LT	5	134.98
CLEAR LAKE AVE/COOK ST TOTAL				1,308.00
ROUNDED TOTAL				8,503

△ REVISED SHEET 2-21-2019



USER NAME = Lin
 PLOT SCALE = 100,0000' / in.
 PLOT DATE = 2/11/2019

DESIGNED - RC
 DRAWN - RC
 CHECKED - FL
 DATE - 12/2018

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

I-55/I-72 STRUCTURE REPAIRS
 SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(84-2) & (84-3) BRR	SANGAMON	98	11
CONTRACT NO. 72197				
ILLINOIS FED. AID PROJECT				