

SUMMARY OF QUANTITIES				NHPP		NHPP		NHPP	
				80% FEDERAL	20% STATE	80% FEDERAL	15% STATE / 5% CITY	100% CITY	100% FRSA
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	MANHOLES	SANITARY		
				0005	0021	0043	0043		
				URBAN	URBAN	URBAN	URBAN		
20200100	EARTH EXCAVATION	CU YD	100	100					
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	148	148					
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	5735	5735					
<del>40600290</del>	<del>BITUMINOUS MATERIALS (TACK COAT)</del>	<del>POUND</del>	<del>5735</del>	<del>5735</del>					
40600370	LONGITUDINAL JOINT SEALANT	FOOT	5699	5699					
40600990	TEMPORARY RAMP	SQ YD	142	142					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	286	286					
40604162	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	1606	1606					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	2	2					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	805	805					
42400800	DETECTABLE WARNINGS	SQ FT	109	109					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	12431	12431					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	18	18					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	294	294					
44000600	SIDEWALK REMOVAL	SQ FT	636	636					

1

\* SPECIALITY ITEM

MODEL SUMMARY 1  
FILE NAME: D2 64P61-Summary of Quantities.dgn

**Kaskaskia**  
Engineering Group LLC  
Professional Engineering Group

USER NAME = zbraun	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN - ZRB	REVISED -
PLOT DATE = 12/08/23	CHECKED - EIJL	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL 2 SMART RESURFACE AND ADA

SCALE: SHEET 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	33RS-3 & (34Y)RS-5	WINNEBAGO	55	5
CONTRACT NO. 64P61				
ILLINOIS FED. AID PROJECT				

# SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNITS	LOCATION	OFFSET	REMARKS
20200100	<u>EARTH EXCAVATION</u>				
	CU YD		IL 2		
	100		341+50 - 345+50		ADA SIDEWALK
	100				
31100500	<u>SUBBASE GRANULAR MATERIAL, TYPE A 6"</u>				
	SQ YD		IL 2		
	148.0		STA 341+50 - 345+50		Under Class C Patches
	148				
40600295	<u>POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)</u>				
	POUND		IL 2		
	723.3		STA 333+51 - 336+50		RT & LT
	1582.1		STA 336+50 - 341+50		RT & LT
	2242.8		STA 341+50 - 345+50		RT & LT
	1186.5		STA 345+50 - 349+92		RT & LT
	5735				
40600370	<u>LONGITUDINAL JOINT SEALANT</u>				
	FOOT		IL 2		
	596.5		STA 333+51 - 336+50		RT & LT
	1647.9		STA 336+50 - 341+50		RT & LT
	2326.6		STA 341+50 - 345+50		RT & LT
	1128.0		STA 345+50 - 349+92		RT & LT
	5699				See TYP SEC
					See TYP SEC
					See TYP SEC
					See TYP SEC
40600990	<u>TEMPORARY RAMP</u>				
	SQ YD		IL 2		
	37.7		STA 333+51 - 333+58		RT & LT
	37.4		STA 349+85 - 349+92		RT & LT
			CLIFTON AVE		
	38.7		STA 8+39 - 8+46		RT & LT
			COMMERCIAL ENTRANCE		
	28.7		STA 11+22 - 11+29		RT & LT
	142				
40601005	<u>HOT-MIX ASPHALT REPLACEMENT OVER PATCHES</u>				
	TON		IL 2		
	285.5		STA 333+51 - 349+92		RT & LT AS NEEDED AND DIRECTED BY THE RESIDENT FOR MAINLINE PATCHES
	286				
40604162	<u>POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70</u>				
	TON		IL 2		
	202.5		STA 333+51 - 336+50		RT & LT
	443.0		STA 336+50 - 341+50		RT & LT
	628.0		STA 341+50 - 345+50		RT & LT
	332.2		STA 345+50 - 349+92		RT & LT
	1606				
40800050	<u>INCIDENTAL HOT-MIX ASPHALT SURFACING</u>				
	TON		IL 2		
	2		STA 342+71 - 342+86		72.27' RT
	2				As Directed by Engineer
42400200	<u>PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH</u>				
	SQ FT		IL 2		
	208.4		STA 342+88 - 343+11		69.29' RT
	58.0		STA 343+21 - 343+34		48.03' RT
	174.6		STA 344+06 - 344+40		44.68' RT
	106.0		STA 343+07 - 343+22		58.27' LT
	85.4		STA 343+93 - 344+08		41.70' LT
	171.8		STA 344+28 - 344+56		60.53' LT
	804				
42400800	<u>DETECTABLE WARNINGS</u>				
	SQ FT		IL 2		
	109.0		STA 341+50 - 345+50		RT & LT
	109				
44000157	<u>HOT-MIX ASPHALT SURFACE REMOVAL, 2"</u>				
	SQ YD		IL 2		
	797.6		STA 333+51 - 336+50		RT
	809.8		STA 333+51 - 336+50		LT
	2135.6		STA 336+50 - 341+50		RT
	1380.1		STA 336+50 - 341+50		LT
	2079.3		STA 341+50 - 345+50		RT
	2591.9		STA 341+50 - 345+50		LT
	1187.3		STA 345+50 - 349+92		RT
	1449.3		STA 345+50 - 349+92		
	12431				
44000161	<u>HOT-MIX ASPHALT SURFACE REMOVAL, 3"</u>				
	SQ YD		IL 2		
	18		STA 341+50 - 345+50		RT
	18				Multi-use Path
44000500	<u>COMBINATION CURB AND GUTTER REMOVAL</u>				
	FOOT		IL 2		
	24.5		STA 343+00 - 343+22		62.27' RT
	19.8		STA 343+09 - 343+23		52.87' RT
	28.2		STA 344+02 - 344+22		37.33' RT
	21.2		STA 344+23 - 344+36		61.41' LT
	200.0		STA 333+51 - 349+92		RT & LT
	294				As Directed by Engineer
44000600	<u>SIDEWALK REMOVAL</u>				
	SQ FT		IL 2		
	162.9		STA 342+97 - 343+16		71.47' RT
	105.7		STA 343+06 - 343+22		63.19' LT
	199.1		STA 344+03 - 344+40		44.67' RT
	168.5		STA 344+27 - 344+56		60.52' LT
	636				
44002232	<u>HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8"</u>				
	SQ YD		IL 2		
	637		STA 333+51 - 349+92		RT & LT
	637				AS NEEDED AND DIRECTED BY THE RESIDENT FOR MAINLINE PATCHES

MODEL: SCHEDULE\_1  
FILE NAME: DD\_64P6\_Schdt-Quant.dwg

**Kaskaskia**  
Engineering Group, LLC  
Professional Engineering Firm

USER NAME = zbraun	DESIGNED -	REVISED - <span style="border: 1px solid black; padding: 2px;">Addendum 1 - 2/19/24</span>
PLOT SCALE =	DRAWN - ZRB	REVISED -
PLOT DATE = 12/08/23	CHECKED - EIJL	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>	
<b>IL 2 SMART RESURFACE AND ADA</b>	
SCALE:	SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	33RS-3 & (34Y)RS-5	WINNEBAGO	55	13
			CONTRACT NO. 64P61	
ILLINOIS FED. AID PROJECT				