



- ### Notes
1. COMPACTION SHALL BE IN ACCORDANCE WITH SECTION 205 OF THE SPECIAL PROVISIONS.
  2. ALL PROPOSED SPECIAL EXCELSIOR BLANKET ARE SHOWN WITH A CIRCLED NUMBER. THE LENGTHS OF EACH OF THESE BLANKETS CAN BE FOUND IN A TABLE ON PAGE 32.
  3. THE CONSTRUCTED TERRACES SHALL HAVE 4' BOTTOM WIDTHS AND 4H:1V UPSLOPES 2' IN HEIGHT. THE SPECIAL EXCELSIOR BLANKET SHALL BE PLACED OVER THE 4' BOTTOM WIDTH AND 4' OF THE UPSLOPE.
- TYPICAL TERRACE  
NOT TO SCALE
4. THE PROPOSED TEMPORARY DITCH CHECK #1 SHALL BE CONSTRUCTED PRIOR TO EARTH EXCAVATION. THE AREA UPSTREAM OF THE DITCH CHECK SHALL BE CLEANED OF SEDIMENT EVERY 3 MONTHS THEREAFTER FOR THE DURATION OF THE CONTRACT. THIS CLEANOUT WORK SHALL BE INCIDENTAL TO THE CONSTRUCTION OF THE DITCH CHECK.

### Legend

	EXISTING CONTOUR
	PROPOSED CONTOUR
	PROPOSED CONSTRUCTION LIMITS
	BASELINE FOR CROSS SECTIONS
	TREE LINE
	SECTION LINE
	OVERHEAD ELECTRIC LINE
	EDGE OF WATER
	EXISTING GRASS LANE
	BORING LOCATION
	EXISTING STRUCTURE
	PROPOSED EXCELSIOR BLANKET (8' WIDTH)

