F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	*	COOK	283	13
STA. 9+713.000		TO STA. 10+151.000		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
* 700-Y-B-R & 70HB-R-1				62897

TREE REMOVAL (OVER 15 UNITS DIA.)

UNIT=25MM

LOCATION			SIZE (MM)	UNIT
RAMP C				
STA.	0+196.904	RT.	1250	50
STA.	0+197.291	RT.	750	30
STA.	0+197.723	RT.	750	30
STA.	0+201.325	RT.	375	15
STA.	0+204.096	RT.	500	20
STA.	0+215.764	RT.	500	20

TREE REMOVAL (OVER 15 UNITS DIA.) TOTAL= 165 UNITS

BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION			AREA (SQ. M.)
IL ROUTE 68			
9+698.000	TO	9+708.9000	124
10+151.000	TO	10+165.000	219

BITUMINOUS SURFACE REMOVAL - BUTT JOINT, TOTAL = 343 SQ. M.

PAVEMENT REMOVAL

LOCATION			AREA (SQ. M.)
IL ROUTE 68			
9+713.000	TO	9+850.000	1,544
9+850.000	TO	9+882.353	509
9+935.116	TO	9+956.821	496
10+045.240	TO	10+100.000	957
10+100.000	TO	10+151.000	385
RAMP A			
0+260.000	TO	0+309.015	336
0+123.000	TO	0+260.000	569
RAMP B			
0+509.247	TO	0+150.000	625
0+150.000	TO	0+300.612	869
RAMP C			
0+060.910	TO	0+225.000	817
0+225.000	TO	0+289.486	411
RAMP D			
0+011.509	TO	0+150.000	813
0+150.000	TO	0+308.501	769

PAVEMENT REMOVAL, SUBTOTAL = 9,100 SQ. M.

TEMPORARY PAVEMENT REMOVAL = 1,522 SQ. M.

PAVEMENT REMOVAL, TOTAL = 10,622 SQ. M.

DRIVEWAY PAVEMENT REMOVAL

LOCATION					AREA (SQ. M.)
IL ROUTE 68					
9+756.612				LT.	107
9+783.711	TO		9+798.50	LT.	4
RAMP C					
0+145.000	TO		0+240.5	RT.	619

DRIVEWAY PAVEMENT REMOVAL, TOTAL = 730 SQ. M.

APPROACH SLAB REMOVAL

LOCATION	AREA SQ. M.
IL ROUTE 68	
9+882.840	114
9+922.859	169
9+957.066	316
10+030.285	326

APPROACH SLAB REMOVAL, TOTAL= 925 SQ. M.

COMBINATION CURB AND GUTTER REMOVAL

LOCATION					LENGTH (METER)
RAMP B					
0+249.253	RT	TO	0+300.612	RT	53
RAMP C					
0+060.910	RT	TO	0+210.700	RT	149

COMBINATION CURB AND GUTTER REMOVAL , TOTAL= 202 METER

MEDIAN REMOVAL

LOCATION				AREA (SQ. M.)
IL ROUTE 68				
9+976.950	TO	10+043.897		81
10+064.604	TO	10+100.000		166
10+100.000	TO	10+203.000		405

MEDIAN REMOVAL, TOTAL = 652 SQ. M.

PAVED SHOULDER REMOVAL

LOCATION					AREA (SQ. M.)
IL ROUTE 68					
9+713.000	LT.	TO	9+850.000	LT.	81.5
9+713.000	RT.	TO	9+850.000	RT.	64.2
9+850.000	RT.	TO	9+876.859	LT.	59.5
9+850.000	RT.	TO	9+887.943	RT.	44.8
10+023.196	LT.	TO	10+047.965	LT.	56.9
10+043.884	RT.	TO	10+055.586	RT.	23.9
10+078.675	LT.	TO	10+100.000	LT.	66.1
10+079.796	RT.	TO	10+100.000	RT.	53.6
10+100.000	LT.	TO	10+151.000	LT.	156.3
10+100.000	RT.	TO	10+151.000	RT.	125.5
RAMP A					
1+16.81	LT.	TO	0+260.000	LT.	463.1
5+21.55	RT.	TO	0+260.000	RT.	418.8
0+260.000	RT.	TO	0+304.176	RT.	149.6
0+260.000	LT.	TO	0+315.912	LT.	153.6
RAMP B					
0+024.372	LT.	TO	0+150.000	LT.	296.2
0+000.000	RT.	TO	0+150.000	RT.	420.2
0+150.000	LT.	TO	0+211.564	LT.	104.1
0+150.000	RT.	TO	0+300.612	RT.	369.4
RAMP C					
0+060.910	RT.	TO	0+225.000	RT.	441.6
0+060.910	LT.	TO	0+225.000	LT.	484.6
0+225.000	RT.	TO	0+284.662	RT.	191.6
0+225.000	LT.	TO	0+292.990	LT.	164.3
RAMP D					
0+018.154	LT.	TO	0+150.000	LT.	366.4
0+003.259	RT.	TO	0+150.000	RT.	440.9
0+150.000	LT.	TO	0+192.085	LT.	110.4
0+150.000	RT.	TO	0+308.501	RT.	329.7

PAVED SHOULDER REMOVAL, TOTAL = 5,637 SQ. M.

STORM SEWER REMOVAL 300MM

LOCATION					LENGTH (METER)
IL RTE 68					
9+972.736	6.6 RT	TO	9+975.051	22.6 RT	16.2
RAMP C					
0+156.606	1.6 LT	TO	0+173.091	11.5 LT	19.2

STORM SEWER REMOVAL 300MM, TOTAL= 35.4 METER

DRAINAGE STRUCTURE REMOVALS

LOCATION	REMOVING CATCH BASINS (EACH)	REMOVING INLETS (EACH)	FLARED END SECTION REMOVAL (EACH)
IL RTE 68			
9+972.736 6.6 RT		1	
10+043.817 10.8 RT		1	
RAMP B			
0+217.806 14.0 RT			1
RAMP C			
0+173.091 11.5 LT	1		

REMOVING CATCH BASINS, TOTAL = 1 EACH

REMOVING INLETS, TOTAL = 2 EACH

FLARED END SECTION REMOVAL, TOTAL = 1 EACH

GUARDRAIL REMOVAL

LOCATION					LENGTH (METER)
IL ROUTE 68					
9+695.83	LT.	TO	9+745.86	LT.	50
9+851.74	LT.	TO	9+874.372	LT.	23
9+846.87	RT.	TO	9+877.67	RT.	31
9+916.37	LT.	TO	9+933.933	LT.	23
9+932.80	RT.	TO	9+954.582	RT.	23
10+025.2	LT.	TO	0+053.62	LT.	35
RAMP A					
0+123.21	LT.	TO	0+238.20	LT.	116
RAMP B					
0+027.32	LT.	TO	0+040.76	LT.	17
0+171.64	LT.	TO	0+301.257	LT.	130
RAMP C					
0+184.67	LT.	TO	0+268.26	LT.	97
RAMP D					
0+019.89	LT.	TO	0+160.367	LT.	136

GUARDRAIL REMOVAL, TOTAL = 681 METER

PAVEMENT MARKING REMOVAL

DESCRIPTION	IL RTE 68	
	9+649.943 TO 9+698.000	10+165.000 TO 10+289.928
100mm DOUBLE SOLID	14.6	
100mm WHITE SKIP DASH		3.6
100mm WHITE OR YELLOW		7.6
150mm WHITE SOLID	3.5	4.8
LETTERS AND SYMBOLS	5.9	
SUBTOTAL=	24.0	16.0

PAVEMENT MARKING REMOVAL, TOTAL= 40.0 SQ M

FENCE REMOVAL

LOCATION				LENGTH (METER)
IL RTE 68				
9+786.053	TO	9+858.012	RT	76

FENCE REMOVAL, TOTAL= 76 METER

REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS

LOCATION	EACH
RAMP A	
0+125.000	1
RAMP C	
0+184.673	1

REMOVAL AND REINSTALLATION OF EXISTING IMPACT ATTENUATORS, TOTAL= 2 EACH

REMOVE RIGHT-OF-WAY MARKERS

LOCATION	UNIT EACH
IL ROUTE 68	
9+749.220 15.2 LT	1
9+836.774 15.3 LT	1
9+855.868 15.1 RT	1
RAMP A	
0+293.037 1.0 RT	1
RAMP C	
0+192.325 3.2 RT	1
0+236.494 1.1 RT	1

REMOVE RIGHT-OF-WAY MARKERS, TOTAL= 6 EACH

BUILDING REMOVAL

	UNIT L SUM
RAMP C STA. 0+207.900, 13.3 RT	
BUILDING REMOVAL NO. 1	1
REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO.1	1
REMOVAL AND DISPOSAL OF NON- FRIABLE ASBESTOS, BUILDING NO.1	1
RAMP C STA. 0+224.300, 16.9 RT	
BUILDING REMOVAL NO. 2	1
REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO.2	1
REMOVAL AND DISPOSAL OF NON- FRIABLE ASBESTOS, BUILDING NO.2	1

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 68

SCHEDULE OF QUANTITIES
REMOVALS - 1

SCALE NTS DRAWN BY RDT

DATE OCTOBER, 2006 CHECKED BY PK

...\c1\sheets\345c101.dgn 10/13/2006 3:34:59 PM