

COUNTY SHEETS NO. RTE. SECTION соок 343 * STA. FED. ROAD DIST. NO. 1 | ILLINOIS FED. AID PROJECT * 700-Y-R & 70HB-R-1 KEY PLAN

UNDERPASS LUMINAIRE WIRING DETAIL (US 14)



PARTIAL ELEVATION (US 14)



1B JUNCTION BOX WIRING DETAIL (US 14)

<u>NOTES</u>

1. REFER TO DRAWING BE-900 FOR SUSPENDED MOUNT UNDERPASS DETAILS.

2. FUSE KITS AND GROUND WIRE SPLICE SHALL BE INCLUDED IN THE PAY ITEM FOR THE JUNCTION BOX.

3. UNDERPASS LUMINAIRES SHALL BE MOUNTED 4.9m ABOVE THE SHOULDER.

4. MOUNT JUNCTION BOX 5M ABOVE GRADE.

5. ALL UNDERPASS LIGHTING CONDUITS ARE ATTACHED TO STRUCTURE.


EQUIPMENT LIST

- 1 450mm × 450mm × 200mm STAINLESS STEEL JUNCTION BOX ATTACHED TO RETAINING WALL.
- 2 150mm x 150mm x 100mm STAINLESS STEEL JUNCTION BOX ATTACHED TO UNDERSIDE OF BRIDGE DECK, TYPICAL.
- 300mm × 250mm × 150mm STAINLESS STEEL JUNCTION BOX ATTACHED TO RETAINING WALL, TYPICAL.
- 4 75mm PVC COATED RGS SLEEVE WITH 30mm UNIT DUCT AND 3*4 & 1*6 GND CONDUCTORS


TAG NOTES

- 1 400mmx400mmx150mm STAINLESS STEEL JUNCTION BOX
- 2 MECHAINCAL SPLICE
- 3 75mm PVC COATED RGS SLEEVE
- 4 30mm UNIT DUCT
- 5 25mm PVC COATED RGS
- 6 QUICK DISCONNECT FUSE KIT WITH 30A FUSE
- 1 OUICK DISCONNECT FUSE KIT WITH SOLID NEUTRAL ASSEMBLY
- 8 *10 COPPER, 600V
- 9 *4 COPPER, 600V
- 10 *6 COPPER GROUND
- ① 300mm × 300mm × 150mm NON-METALLIC JUNCTION BOX
- 12 50mm PVC COATED RGS CONDUIT
- 1 65 mm EMBEDDED PVC CONDUIT

UNDERPASS LUMINAIRE WIRING DETAIL (UPRR)



LT-18 OF 19



rawir M / king Files∰Dr 250.000000 k 14 US er US 1 over U 22 PM 68 ove IL 68 o 3:40:27 = 1