



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 27, 2007

SUBJECT: FAI Route 39 (I-39)  
Section (141 / 201) Fiber Optics  
Ogle / Winnebago County  
Contract No. 64C83  
Item No. 117, March 9, 2007 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 6 & 7 of the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: J. E. Crowe, Dep. Dir. Highways, Dist 2 Engineer; Roger Driskell;  
Estimates; Design & Environment File

TBW:RS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

64C83

State Job # - C-92-032-07

PPS NBR - ITS

Project Number

Route

County Name - OGLE - -

FAI 39

Code - 141 - -

District - 2 - -

Section Number - (141/201)FIBER OPTICS

| Item Number | Pay Item Description  | Unit of Measure | Quantity                      | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-------------------------------|---|------------|---|-------------|
| XX005765    | FIBER OPTIC HANDHOLE  | EACH            | 80.000                        |   |            |   |             |
| X0325690    | AR LT FOC DB J/SA 96S | FOOT            | 442,530.000                   |   |            |   |             |
| X0325700    | CON ATBS 4 FG RE EP S | FOOT            | 3,085.000                     |   |            |   |             |
| * DELETED   |                       |                 |                               |   |            |   |             |
| Z0048665    | RR PROT LIABILITY INS | L SUM           | 1.000                         |   |            |   |             |
| 20800150    | TRENCH BACKFILL       | CU YD           | 31.000                        |   |            |   |             |
| 21101615    | TOPSOIL F & P 4       | SQ YD           | 29,110.000                    |   |            |   |             |
| 25000210    | SEEDING CL 2A         | ACRE            | 6.000                         |   |            |   |             |
| 25000400    | NITROGEN FERT NUTR    | POUND           | 540.000                       |   |            |   |             |
| 25000500    | PHOSPHORUS FERT NUTR  | POUND           | 540.000                       |   |            |   |             |
| 25000600    | POTASSIUM FERT NUTR   | POUND           | 540.000                       |   |            |   |             |
| 28000250    | TEMP EROS CONTR SEED  | POUND           | 4,213.000                     |   |            |   |             |
| 50200400    | ROCK EXC STRUCT       | CU YD           | 1,259.100                     |   |            |   |             |
| 60100915    | PIPE DRAINS 6         | FOOT            | 12.000                        |   |            |   |             |
| 60100925    | PIPE DRAINS 8         | FOOT            | 4.000                         |   |            |   |             |
|             |                       |                 | * REVISED : FEBRUARY 28, 2007 |   |            |   |             |

## TABLE OF CONTENTS

|                                                                                                           |    |
|-----------------------------------------------------------------------------------------------------------|----|
| LOCATION OF PROJECT .....                                                                                 | 1  |
| DESCRIPTION OF PROJECT.....                                                                               | 1  |
| TRAFFIC CONTROL PLAN.....                                                                                 | 1  |
| ARMORED LOOSE TUBE ENHANCED SINGLE-MODE FIBER OPTIC CABLE – DOUBLE<br>JACKET/SINGLE ARMOR, 96 STRAND..... | 2  |
| FIBER OPTIC HANDHOLE.....                                                                                 | 4  |
| CONDUIT ATTACHED TO BRIDGE STRUCTURE, 4”, FIBERGLASS REINFORCED EPOXY, SPECIAL5<br>COMPLETION DATE.....   | 6  |
| ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE).....                                                    | 7  |
| PAYMENTS TO SUBCONTRACTORS (BDE) .....                                                                    | 8  |
| RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....                                                        | 9  |
| RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE).....                                             | 10 |
| SEEDING (BDE) .....                                                                                       | 12 |
| SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE).....                                               | 13 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....                                                            | 14 |
| PROJECT LABOR AGREEMENT .....                                                                             | 16 |
| STORM WATER POLLUTION PREVENTION PLAN.....                                                                | 30 |

Revised 02/27/2007

Basis of Payment. This work will be paid for at the contract unit price per foot for CONDUIT ATTACHED TO BRIDGE STRUCTURE, 4", FIBERGLASS REINFORCED EPOXY, SPECIAL, which shall include all material, labor, and equipment to complete this work. The PE inner ducts, and the two junction boxes at the Kishwaukee River bridge will not be paid for separately, but will be included in the cost of this item.

**COMPLETION DATE**

Effective November 21, 2006

The Contractor shall perform his work in such a manner that the project is completed on or prior to November 19, 2007. The project shall have all fiber optic installed before it is considered complete. If the Contractor fails to complete the project by the above completion date, the Contractor shall be charged liquidated damages by the Department of ONE THOUSAND TWO HUNDRED DOLLARS (\$1,200.00) a day for each day the project is not opened beyond the opening date. If in the event additional traffic control and protection is required to open the road or after the road is open to traffic, it shall be at no additional cost to the Department.

The Contractor will be allowed 15 working days, after the November 19, 2007 completion date to complete landscaping.

Revised 02/27/2007

**ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE)**

Effective: January 1, 2007

Page 60 Article 109.07(a). In the second line of the first paragraph change “amount” to “quantity”.

Page 207 Article 406.14. In the second line of the second paragraph change “MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS, of the mixture composition specified;” to “MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS;”.

Page 398 Article 540.07(b). Add the following two paragraphs after the third paragraph:

“Excavation in rock will be measured for payment according to Article 502.12.

Removal and disposal of unstable and/or unsuitable material below plan bedding grade will be measured for payment according to Article 202.07.”

Page 398 Article 540.08. Add the following two paragraphs after the fifth paragraph:

“Excavation in rock will be paid for according to Article 502.13.

Removal and disposal of unstable and/or unsuitable material below plan bedding grade will be paid for according to Article 202.08.”

Page 465 Article 551.06. In the second line of the first paragraph change “or” to “and/or”.

Page 585 Article 701.19(a). Add “701400” to the second line of the first paragraph.

Page 586 Article 701.19(c). Delete “701400” from the second line of the first paragraph.

Page 586 Article 701.19. Add the following subparagraph to this Article:

“(f) Removal of existing pavement markings and raised reflective pavement markers will be measured for payment according to Article 783.05.”

Revised 02/27/2007