

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	102BR-1, 102BR-2, 102BR-3 D	WINNEBAGO	52	3
STA.		TO STA.		
FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT		

CONTRACT NO. 64C93

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%
				ROADWAY 1000-2A	BRIDGE SN 101-0146	BRIDGE SN 101-0147	BRIDGE SN 101-0148	IMPACT ATTENUATORS
20200100	EARTH EXCAVATION	CU YD	60	60				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	30	30				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	75	75				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	73	73				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	868	868				
44004250	PAVED SHOULDER REMOVAL	SQ YD	545	545				
44000300	CURB REMOVAL	FOOT	113	113				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	20	20				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	727	727				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	3		1	1	1	
50102400	CONCRETE REMOVAL	CU YD	15.3		5.1	5.1	5.1	
50300225	CONCRETE STRUCTURES	CU YD	15.3		5.1	5.1	5.1	
50300260	BRIDGE DECK GROOVING	SQ YD	930		310	310	310	
50300300	PROTECTIVE COAT	SQ YD	930		310	310	310	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	8,352		2,784	2,784	2,784	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13,440		4,480	4,480	4,480	
50800515	BAR SPLICERS	EACH	270		90	90	90	
50901050	STEEL RAILING, TYPE SM	FOOT	465		155	155	155	
50901125	STEEL RAILING (TEMPORARY)	FOOT	262.5	262.5				
51500100	NAME PLATES	EACH	3		1	1	1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	216		72	72	72	
58700300	CONCRETE SEALER	SQ FT	552		184	184	184	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1,012.5	1,012.5				
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	12	12				
* 63100110	TRAFFIC BARRIER TERMINAL, TYPE 11	EACH	6	6				
63200310	GUARDRAIL REMOVAL	FOOT	1,542	1,542				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2 + 2 +	2 + 2 +				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10				

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%	FHWA 80% STATE 20%
				ROADWAY 1000-2A	BRIDGE SN 101-0146	BRIDGE SN 101-0147	BRIDGE SN 101-0148	IMPACT ATTENUATORS
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	2				
70106700	TEMPORARY RUMBLE STRIP	EACH	10	10				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	694	694				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	8,256	8,256				
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	126	126				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3,236	3,236				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	925.0	925.0				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	837.5	837.5				
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	13,801	13,801				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3	3				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3		1	1	1	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	48	48				
78300100	PAVEMENT MARKING REMOVAL	SO FT	4,603	4,603				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6				
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	156		52	52	52	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12					12
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6					6
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	25		25			
X5030305	CONCRETE WEARING SURFACE, 5"	SO YD	930		310	310	310	

* SPECIALTY ITEMS

PLAN
DATE: _____
BY: _____
CHECKED: _____
DATE: _____
NO. _____
FILE NAME: _____

PROFILE
DATE: _____
BY: _____
CHECKED: _____
DATE: _____
NO. _____
FILE NAME: _____

PLOT SCALE: 5/8" = 1' / IN.
PLOT DATE: Mon Dec 18 07:55:39 2006
PLOT TIME: 8:15 AM
PLOT BY: JMC
PLOT FILE: 70103815.DWG
MODEL NAME: 70103815.DWG

REVISIONS 2/15/07

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.S. ROUTE 55 (INTERSTATE 70)
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. NONE
HORIZ. NONE
DATE: DECEMBER 15, 2006

DRAWN BY: JMC
CHECKED BY: DWB