

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	1 VBR	BUREAU	72	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:		
			URBAN TOTAL QUANTITY	X171-5B	
				ROADWAY 80% FED/ 20% STATE	BRIDGE
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	225	225	0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	0
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2	0
* 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	2	2	0
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	22	22	0
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	0
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	0
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	16	16	0
67100100	MOBILIZATION	L SUM	1	1	0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	0
70103815	TRAFFIC CONTROL AND SURVEILLANCE	CAL DA	120	120	0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	192	192	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5560	5560	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	64	64	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	650	650	0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	650	650	0
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2760	2760	0
78200410	GUARDRAIL MARKERS, TYPE A	EACH	3	3	0
78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6	0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	0
78300105	PAVEMENT MARKING REMOVAL	FOOT	1100	1100	0
X0323120	BRIDGE MONITORING	EACH	1	0	1
X0323149	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	3429	0	3429
* X0323814	SANITARY SEWER REMOVAL, 18"	FOOT	228	228	0
* X0324446	DUCTILE IRON WATER MAIN FITTING - 10", 11 1/4 DEGREE BEND	EACH	1	1	0
* X0324447	DUCTILE IRON WATER MAIN FITTING - 10", 22 1/2 DEGREE BEND	EACH	1	1	0
* X0324448	DUCTILE IRON WATER MAIN FITTING - 10", 45 DEGREE BEND	EACH	6	6	0
51202305	DRIVING PILES	FOOT	845	0	845
* X0325386	SANITARY SEWER PVC (C-900) 18"	FOOT	141	141	0
* X0325390	DUCTILE IRON WATER MAIN FITTING - COUPLER	EACH	2	2	0
X0325391	EXPANDED POLYSTYRENE FILL	CU YD	515	0	515
* X0325392	DUCTILE IRON WATER MAIN FITTING - 6" X 2" REDUCER	EACH	1	1	0
X0329862	REMOVE EXISTING MANHOLE	EACH	2	2	0
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	220	220	0
X4020700	AGGREGATE SURFACE COURSE, TYPE B 8"	SQ YD	521.3	521.3	0
* XX001468	PVC SANITARY SEWER, 18"	FOOT	240	240	0
* XX003772	CUT AND CAP EXISTING 10" WATER MAIN	EACH	1	1	0
* XX005006	DUCTILE IRON WATER MAIN FITTING - 10" X 10" TEE	EACH	1	1	0
* XX005009	DUCTILE IRON WATER MAIN FITTING - 10" X 6" REDUCER	EACH	1	1	0

* SPECIALTY ITEMS
 ** SFTY - 3N
 Δ REVISED 2/27/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 11/29/2006
 PLOT SCALE = AS SHOWN
 USER NAME = BUSEBA