

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
(34)R,DM&X-TRS&BR				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE:							
				I000-2A	X171-5B	X071-2A	Y007	SFTY-1A	SFTY-1B	SFTY-1B	
				ROADWAY	SN 050-0095	SN 050-0094	STORM SEWER UPSIZE	SIDEWALK REMOVAL	DETECTABLE WARNINGS	SIDEWALK	
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	100% CITY	50% STATE 50% CITY	50% STATE 50% CITY	
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	969								969
42400800	DETECTABLE WARNINGS	SQ FT	150								150
44000100	PAVEMENT REMOVAL	SQ YD	4629	4629							
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	995	995							
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2221	2221							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	580	580							
44000300	CURB REMOVAL	FOOT	979	979							
44000400	GUTTER REMOVAL	FOOT	456	456							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1163	1163							
44000600	SIDEWALK REMOVAL	SQ FT	8367	8088				279			
44004250	PAVED SHOULDER REMOVAL	SQ YD	231	231							
44201765	CLASS D PATCHES, TYPE II 10 INCH	SQ YD	57	57							
44201769	CLASS D PATCHES, TYPE III 10 INCH	SQ YD	55	55							
44201803	CLASS D PATCHES, TYPE II 13 INCH	SQ YD	26	26							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	273	273							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1						
50102400	CONCRETE REMOVAL	CU YD	61.2			61.2					
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	716	716							
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1			1					
50105210	REMOVE EXISTING CULVERTS	FOOT	61	61							
50200100	STRUCTURE EXCAVATION	CU YD	309			309					
50300100	FLOOR DRAINS	EACH	10			10					
50300225	CONCRETE STRUCTURES	CU YD	70.2			70.2					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	356.3			356.3					
50300260	BRIDGE DECK GROOVING	SQ YD	930			930					
50300280	CONCRETE ENCASEMENT	CU YD	3.2			3.2					
50300300	PROTECTIVE COAT	SQ YD	1210			1210					
50325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	88			88					
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1					
50500505	STUD SHEAR CONNECTORS	EACH	3984			3984					
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	10			10					
50501110	STRUCTURAL STEEL REMOVAL	POUND	3460			3460					
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1			1					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	102,570			102,570					
50604401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1			1					
50800515	BAR SPLICERS	EACH	1799			1799					
50900605	HANDRAIL REMOVAL	FOOT	788.5	788.5							
50901720	BICYCLE RAILING	FOOT	457	168		289					
50901750	PARAPET RAILING	FOOT	289			289					
51100300	SLOPE WALL 6 INCH	SQ YD	142			142					
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	325			325					
51202305	DRIVING PILES	FOOT	325			325					

△ REVISED 2/15/07
*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SCALE: VERT. _____
 HORIZ. _____
DATE _____ DRAWN BY _____
 CHECKED BY _____