CONTRACT NO. 66617

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	*	LASALLE	126	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (34)R,DM&(X-1)RS&BR

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000-2A ROADWAY 80% FED 20% STATE	X171-5B SN 050-0095 80% FED 20% STATE	X071-2A SN 050-0094 80% FED 20% STATE	Y007 STORM SEWER UPSIZE 100% CITY	SFTY-1A SIDEWALK REMOVAL 100% CITY	SFTY-1B DETECTABLE WARNINGS 50% STATE 50% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY
51203600	TEST PILE STEEL HP 12X53	EACH	1			1				
51205200	TEMPORARY SHEET PILING	SQ FT	3274	2743		531				
51500100	NAME PLATES	EACH	1			1				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	38			38				
52000325	NEOPRENE EXPANSION JOINT 2 1/2"	FOOT	38			38				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6			6				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6			6				
52100520	ANCHOR BOLTS, 1"	EACH	60			60				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1						
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	1	1						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	254	254						
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	13	13						
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	47	47						
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	52	52						
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	9	9						
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	254	~~190.5~~ 169			~~63.5~~ 85			
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	360	~~241~~ 221			~~119~~ 139			
550A0320	STORM SEWERS, CLASS A, TYPE 2 8"	FOOT	19	19						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	39	39						
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	17	17						
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	44	44						
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	196	~~147~~ 134			~~49~~ 62			
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	340	~~228~~ 212			~~112~~ 128			
550A2630	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 54"	FOOT	24	~~16~~ 17			~~8~~ 7			
55100300	STORM SEWER REMOVAL 8"	FOOT	194	194						
55100500	STORM SEWER REMOVAL 12"	FOOT	613	613						
55100900	STORM SEWER REMOVAL 18"	FOOT	48	48						
* 56106300	ADJUSTING WATER MAIN 6"	FOOT	10	10						
56109210	WATER VALVES TO BE ADJUSTED	EACH	5	5						
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	165	165						
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1						
58700300	CONCRETE SEALER	SQ FT	24			24				
59000200	EPOXY CRACK INJECTION	FOOT	28			28				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66			66				
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	80			80				
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1						
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						

REVISED 2/15/07

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

12/18/2006 10:56:43 AM
c:\projects\sp0170\details.dgn