

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
702	(113B)	WOODFORD	38	3
STA. 13+30		TO STA. 17+00		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				FAP 714 80% FEDERAL 20% STATE	S.N. 102-0018 80% FEDERAL 20% STATE
			CONSTRUCTION TYPE CODE		
			1000-2A	X080-2A	
20400800	FURNISHED EXCAVATION	CU YD.	154	154	
25000200	SEEDING, CLASS 2	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25100630	EROSION CONTROL BLANKET	SQ YD.	968	968	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20	
28000400	PERIMETER EROSION BARRIER	FOOT	600	600	
31100300	SUB-BASE GRANULAR MATERIAL TYPE A 4"	SQ. YD.	140	140	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ. YD.	140	140	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.15	0.15	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	9	9	
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	194	194	
40600990	TEMPORARY RAMP	SQ. YD.	44	44	
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	34	34	
42001300	PROTECTIVE COAT	SQ. YD.	181		181
44000100	PAVEMENT REMOVAL	SQ. YD.	140	140	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD.	2.0		2.0
50300225	CONCRETE STRUCTURES	CU. YD.	2.6		2.6
50300260	BRIDGE DECK GROOVING	SQ. YD.	172		172
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ. FT.	299		299
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	1,627		1,627
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,640		2,640
50800515	BAR SPLICERS	EACH	48		48
50901050	STEEL RAILING, TYPE SM	FOOT	165		165
51500100	NAME PLATES	EACH	1		1
59000200	EPOXY CRACK INJECTION	FOOT	30		30
*63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	75		75
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1. SPECIAL (TANGENT)	EACH	4		4
67100100	MOBILIZATION	L. SUM	1		1
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	L. SUM	1		1
70101205	TRAFFIC CONTROL AND PROTECTION STANDARD 701321, SPECIAL	EACH	1		1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	125		125
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2245		2245

SUMMARY OF QUANTITIES

CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				FAP 702 80% FEDERAL 20% STATE	S.N. 102-0018 80% FEDERAL 20% STATE
			CONSTRUCTION TYPE CODE		
			1000-2A	X080-2A	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	798	798	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	275	275	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275	
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1776	1776	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
78201000	TERMINAL MARKER DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	513	513	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	2	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	115	115	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ. FT.	13		13
X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	181		181
52000110	PREFORMED JOINT STRIP SEAL	FOOT	41		41
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1		1
Z0030250	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	26		26

* SPECIALTY ITEM
● SFTY-3N

SUMMARY OF QUANTITIES
IL ROUTE 117 OVER WALNUT CREEK
F.A.P. RTE. 702 - SECTION (113B)
WOODFORD COUNTY
STA. 15+45.00
S.N. 102-0018

FILE NAME: SO (REV. 12/28/03)