

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	129 B-2	MCLEAN	34	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 70519

SUMMARY OF QUANTITIES			S.N. 057-0190 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X080-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	135
40600300	AGGREGATE (PRIME COAT)	TON	3
40600990	TEMPORARY RAMP	SO YD	144
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	6
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	112
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	533
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,315
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	177
44000600	SIDEWALK REMOVAL	SO FT	508
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	0.3
50300100	FLOOR DRAINS	EACH	3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	24.8
50300260	BRIDGE DECK GROOVING	SO YD	661
50300300	PROTECTIVE COAT	SO YD	746
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	6,453
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10,200
50800515	BAR SPLICERS	EACH	172
50900105	ALUMINUM RAILING, TYPE L	FOOT	75
50901050	STEEL RAILING, TYPE SM	FOOT	87
51500100	NAME PLATES	EACH	1
60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	177
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	1
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	50
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	344

SUMMARY OF QUANTITIES			S.N. 057-0190 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE X080-2A
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	91
70400100	TEMPORARY CONCRETE BARRIER	FOOT	230
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	220
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	SO FT	109
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,912
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	90
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	245
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	81
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6
* 78100300	REPLACEMENT REFLECTOR	EACH	67
* 78200405	GUARDRAIL MARKERS	EACH	8
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
78300100	PAVEMENT MARKING REMOVAL	SO FT	1,503
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	26
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	136
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	38
81030100	CONDUIT SPLICE	EACH	1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	136
* 87301515	ELECTRIC CABLE IN CONDUIT LEAD-IN, NO. 18, 3 PAIR	FOOT	300
* 87900200	DRILL EXISTING HANDHOLE	EACH	3
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	215
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	75
X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	180
X0325491	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC (SCHEDULE 80)	FOOT	180
X5030305	CONCRETE WEARING SURFACE 5"	SO YD	671
* XX002094	REMOVE AND REINSTALL FIBER OPTIC CABLE IN CONDUIT	L SUM	1
△ 20030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2
△ 20030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2
X0325674	REMOVAL OF TEMPORARY CURB, SALVAGE	FOOT	125

△ SFTY-3N
* SPECIALTY ITEM

SUMMARY OF QUANTITIES

FAP ROUTE 693 (IL 9)
SECTION 129 B-2
MCLEAN COUNTY

CUMMINS ENGINEERING CORPORATION

JOB #: 2114.5
FILE: 21140TY.DGN
DATE: 12/18/06