



LOCATION	TYPE	PAVEMENT MARKING TAPE, TYPE III 4"		PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	WORKZONE PAVEMENT MARKING REMOVAL SQ FT
		WHITE FOOT	YELLOW FOOT			
WESTBOUND LANES						
STA 65+40 TO STA 66+04	LEFT TURN LANE LINE	64				22
STA 65+58	LEFT TURN ARROW			15.6		16
STA 66+04	LEFT TURN ARROW			15.6		16
STA 65+40 TO STA 71+80	MEDIAN EDGE LINE		640			214
EASTBOUND LANES						
STA 64+68 TO STA 65+40	LANE EXTENSION		26			9
STA 65+40 TO STA 71+80	MEDIAN EDGE LINE		640			214
STA 70+37 TO STA 71+80	LEFT TURN LANE LINE	143				48
STA 70+73	LEFT TURN ARROW			15.6		16
STA 71+00	LEFT TURN ARROW			15.6		16
STA 71+62	LEFT TURN ARROW			15.6		16
STA 64+68 TO STA 65+40	LANE EXTENSION LINE	26				9
STA 65+40 TO STA 71+31	OUTSIDE EDGE LINE	591				197
TOTAL		824	1,306	78		793

QUANTITIES FOR PLACEMENT AND REMOVAL OF TEMPORARY PAVEMENT MARKINGS ARE INCLUDED FOR INFORMATION ONLY. PLACING MAINTAINING AND REMOVING THESE ITEMS WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST FOR TRAFFIC CONTROL AND PROTECTION (SPECIAL).

TRAFFIC CONTROL LEGEND		TEMPORARY PAVEMENT MARKING LEGEND	
	TYPE III BARRICADE WITH TWO FLASHING LIGHTS		4" SOLID (YELLOW)
	POST MOUNTED SIGN		4" DOUBLE YELLOW (NARROW)
	VERTICAL BARRICADES WITH STEADY BURN MONODIRECTIONAL OR BIDIRECTIONAL LIGHT AT 25 FOOT CENTERS		4" SKIP DASH (WHITE)
	FLASHING LIGHT		4" SOLID (WHITE)
	WORK ZONE		4" LANE EXTENSION (WHITE)
	VERTICAL PANEL WITH STEADY BURNING LIGHT AT 20 FOOT CENTERS ON TAPER		LEFT TURN ARROW (WHITE)
	CRYSTAL MONODIRECTIONAL REFLECTORS AT 20 FOOT CENTERS		
	TEMPORARY CONCRETE BARRIER		
	FLEXIBLE DELINEATORS AT 25 FOOT CENTERS		
	TYPE B ARROW BOARD		

TEMPORARY PAVEMENT MARKING LAYOUT					
WESTBOUND LANES			EASTBOUND LANES		
STATION	OUTSIDE EDGE OF PAVEMENT	MEDIAN EDGE OF PAVEMENT	STATION	MEDIAN EDGE OF PAVEMENT	OUTSIDE EDGE OF PAVEMENT
69+00	EXISTING	-19.52	69+00	-19.10	-5.36
69+25	EXISTING	-18.89	69+25	-17.20	-2.49
69+50	EXISTING	-17.98	69+50	-14.24	1.45
69+75	EXISTING	-16.85	69+75	-10.24	6.42
70+00	EXISTING	-15.68	70+00	-5.40	12.23
70+25	EXISTING	-14.53	PRC +09.67	-3.31	-
70+50	EXISTING	-13.37	PRC +13.7	-	15.76
70+75	EXISTING	-12.22	70+25	-0.16	18.62
71+00	EXISTING	-11.07	70+50	3.84	23.94
71+25	EXISTING	-9.93	70+75	6.50	27.88
71+50	EXISTING	-8.84	71+00	7.83	30.50
PT +67	EXISTING	-8.00	PT +12.82	8.00	-
71+80	EXISTING	-8.00	71+25	8.00	31.82
			PT +31.17	-	32.00
			71+50	8.00	
			71+75	8.00	
			71+80	8.00	

SHEET 2 OF 2

**TRAFFIC CONTROL AND PROTECTION
STAGE 1**

FAP ROUTE 693 (IL 9)
SECTION 129 B-2
MCLEAN COUNTY

CUMMINS ENGINEERING CORPORATION	JOB #: 2114.5 FILE: 2114.5STAGE1REV DATE: 12/07/06
---------------------------------	--