

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	VERMILION	105	4

* D5 CABLE GUARD 2007-1

SUMMARY OF QUANTITIES

LOCATION OF WORK

RURAL	URBAN
I-74	I-74
STA. 1508+00	STA. 2002+00
TO	TO
STA. 1575+00	STA. 2031+50
90% FEDERAL	90% FEDERAL
10% STATE	10% STATE

CONSTRUCTION TYPE CODE

SFTY-4A SFTY-4A

CODE NO.	ITEM	UNIT	TOTAL	QUANTITY	QUANTITY
* X0325667	WEED CONTROL MOWING STRIP, SPECIAL	SQYD	3846.0	2801.0	1045.0
20200100	EARTH EXCAVATION	CU YD	364.0	325.0	39.0
20400800	FURNISHED EXCAVATION	CUYD	5356.0	3450.0	1906.0
* 25000200	SEEDING CLASS 2	ACRE	6.4	4.6	1.8
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	576.0	414.0	162.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	576.0	414.0	162.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	576.0	414.0	162.0
* 25100115	MULCH METHOD 2	ACRE	12.8	9.2	3.6
* 25100630	EROSION CONTROL BLANKET	SQYD	164.0	24.0	140.0
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	6.4	4.6	1.8
28000300	TEMPORARY DITCH CHECKS	EACH	15.0	5.0	10.0
28000500	INLET AND PIPE PROTECTION	EACH	6.0	4.0	2.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1539.0	1121.0	418.0
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	3.0	3.0	0.0
54248515	CONCRETE COLLAR	EACH	7.0	7.0	0.0
60108100	PIPE UNDERDRAIN, 4" SPECIAL	FOOT	215.0	174.0	41.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0	2.0	2.0
67100100	MOBILIZATION	LSUM	1.0	0.5	0.5
X0325588	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	L SUM	1.0	1.0	0.0
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	8629.0	6302.0	2327.0
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	6.0	2.0	4.0
X0484300	MEDIAN INLET BOX REMOVAL	EACH	3.0	3.0	0.0
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	LSUM	1.0	0.5	0.5
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0	14.0	14.0
XX004373	REMOVE AND RELOCATE INLETS	EACH	1.0	1.0	0.0

*