

# SUMMARY OF QUANTITIES

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	7
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
84-9-41A, HBK, BY, BY-1 * 02-00382-02-PV				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY			STRUCTURE						
				MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00	MACARTHUR EXTENSION & I-72 INTERCHANGE	MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512)	INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008)	MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009)	MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513)	I-72 INTERCHANGE RAMP B & C OVER U.P. RAILROAD (S.N. 084-0514 EB, S.N. 084-0516) FUNDING - 1M	I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB)	FUNDING - 1M	FUNDING - 1M
				50% STATE / 50% CITY	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	
50200100	STRUCTURE EXCAVATION	CU YD	3858.5										
50300100	FLOOR DRAINS	EACH	16								4	12	
50300225	CONCRETE STRUCTURES	CU YD	2621.9					1076.8	68.3		379.4	757.4	340.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3194					1073			952.5	511.2	657.3
50300260	BRIDGE DECK GROOVING	SQ YD	7732					2103			2248	1415	1966
50300280	CONCRETE ENCASEMENT	CU YD	40.9					13.3			12.6	10.6	4.4
50300300	PROTECTIVE COAT	SQ YD	10370					2931			2910	2027	2502
50400735	FURNISH AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	7924.5					3859.5			4065.0		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3170					3170					
50500505	STUD SHEAR CONNECTORS	EACH	18225								7515	10710	
* 50501110	STRUCTURAL STEEL REMOVAL	POUND	2920										2920
50800105	REINFORCEMENT BARS	POUND	65670							65670			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1033700					335340	13520		263260	233480	188100
50800515	BAR SPLICERS	EACH	3403					862			800	136	1605
51100100	SLOPE WALL 4 INCH	SQ YD	1423								1187	84	152
* 51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	5022					1727	245			1068	1982
51201400	FURNISHING STEEL PILES HP10X42	FOOT	2290						865				1425
51201500	FURNISHING STEEL PILES HP10X57	FOOT	4895								1640	3255	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	2322					2322					
51201700	FURNISHING STEEL PILES HP12X74	FOOT	4760					2516			2244		
51202305	DRIVING PILES	FOOT	14267					4838	865		3884	3255	1425
51203400	TEST PILE STEEL HP10X42	EACH	10						4				6
51203500	TEST PILE STEEL HP10X57	EACH	11								1	10	
51203600	TEST PILE STEEL HP12X53	EACH	2					2					
51203700	TEST PILE STEEL HP12X74	EACH	4					2			2		
* 51205200	TEMPORARY SHEET PILING	SQ FT	3441					1380				956	1105
51500100	NAME PLATES	EACH	7					1	1		1	2	2

\* PAY ITEM REQUIRES A SPECIAL PROVISION

12/14/2005 14:58 Job: 02-00382-02-PV/Urban/60hours.dgn  
 © Copyright Hanson Professional Services Inc. 2008  
**HANSON**  
 LAYOUT CLG 12/29/05  
 DRAWN CLG 12/29/05  
 REVIEWED JAD/JMI 01/29/06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES -3  
 FAI-72, MACARTHUR BLVD  
 SEC NO. 02-00382-02-PV  
 SEC NO. (84-9-41A, HBK, BY, BY-1)  
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE 12/14/2006

DRAWN BY CLG  
 CHECKED BY JAD