

# SUMMARY OF QUANTITIES

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		STRUCTURE					
				MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00	MACARTHUR EXTENSION & I-72 INTERCHANGE	MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512)	INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008)	MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009)	MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513)	I-72 INTERCHANGE RAMP B & C OVER U.P. RAILROAD (S.N. 084-0514 EB, S.N. 084-0516)	I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB)
				FUNDING - 1M 50% STATE / 50% CITY	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE	FUNDING - 1M 90% FED / 10% STATE
				CO00	CO00	X181-5B	X932-5B	X928-2A	X781-2A	X171-5B	X171-5B
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	2589	2589							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	856	142	714						
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	2167	699	1468						
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	552	537	15						
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	813	813							
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	911	911							
550A0510	STORM SEWERS, CLASS A, TYPE 2 66"	FOOT	1198	1198							
550A0790	STORM SEWERS, CLASS A, TYPE 3 54"	FOOT	375	375							
550A0800	STORM SEWERS, CLASS A, TYPE 3 60"	FOOT	1891	1891							
550A0820	STORM SEWERS, CLASS A, TYPE 3 72"	FOOT	300	300							
550A1380	STORM SEWERS, CLASS A, TYPE 5 66"	FOOT	496	496							
550A1560	STORM SEWERS, CLASS A, TYPE 6 18"	FOOT	563	563							
550A1690	STORM SEWERS, CLASS A, TYPE 6 72"	FOOT	1302	446	856						
55101200	STORM SEWER REMOVAL 24"	FOOT	158	150	8						
58700300	CONCRETE SEALER	SQ FT	668				159			411	98
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	684			265		238		106	75
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	11	4	7						
60100915	PIPE DRAINS 6"	FOOT	40	20	20						
60100925	PIPE DRAINS 8"	FOOT	40	20	20						
60100945	PIPE DRAINS 12"	FOOT	40	20	20						
* 60102005	PIPE DRAINS 12" (SPECIAL)	FOOT	3696	1083	2613						
60107600	PIPE UNDERDRAINS 4"	FOOT	3267	555	2712						
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	656	206	450						
* 60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	1504			350		441	303	202	208
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1							
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	4		4						

\* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES -5  
 FAI-72, MACARTHUR BLVD  
 SEC NO. 02-00382-02-PV  
 SEC NO. (84-9-4)A,HBK,BY,BY-1  
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT.      DRAWN BY CLG  
 HORIZ.              CHECKED BY JAD  
 DATE 12/14/2006



© Copyright Hanson Professional Services Inc. 2006

12/14/2006  
 1089 jobs 0655022-achm-000000-60000000

LAYOUT	CLG	04/25/06
DRAWN	CLG	04/25/06
REVIEWED	JAD/JAN	04/25/06