CONTRACT *72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	ROADWAY: MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00 50% STATE / 50% CITY	ROADWAY: MACARTHUR EXTENSION & I-72 INTERCHANGE FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: I-72 INTERCHANGE RAMP B & C OVER U.P RAILROAD (S.N. 084-0514 EB, S.N. 084-0516) FUNDING - IM 90% FED / 10% STATE	STRUCTURE: I-72 EB & WB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 WB) FUNDING - IM 90% FED / 10% STATE
				C000	C000	X181-5B	X932-5B	X928-2A	X781-2A	X171-5B	X171-5B
* 60220200	MANHOLES, TYPE A, 4'-DIAMETER	EACH	7	7							
* 60222900	MANHOLES, TYPE A, 5'-DIAMETER	EACH	6	3	3						
* 60224075	MANHOLES, TYPE A, 6'-DIAMETER	EACH	6	5	1						
* 60229000	MANHOLES, SPECIAL, TYPE 1	EACH	4	2	2						
* 60229100	MANHOLES, SPECIAL, TYPE 2	EACH	4	4							
* 60229200	MANHOLES, SPECIAL, TYPE 3	EACH	3	3							
* 60229300	MANHOLES, SPECIAL, TYPE 4	EACH	2	2							
* 60229400	MANHOLES, SPECIAL, TYPE 5	EACH	3	3							
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2							
60237480	INLETS, TYPE A, TYPE 37 GRATE	EACH	5	3	2						
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	42	42							
60240330	INLETS, TYPE B, TYPE 37 GRATE	EACH	15	14	1						
* 60246705	MEDIAN INLET (604101), SPECIAL	EACH	1		1						
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1		1						
60260100	INLETS TO BE ADJUSTED	EACH	2								2
60403200	GRATES, TYPE 37	EACH	27	23	4						
60404300	FRAMES AND GRATES, TYPE 3	EACH	2	2							
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	7	4	3						
60500060	REMOVING INLETS	EACH	2		2						
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	243.0	243.0							
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2		2						
* 60900245	TYPE C INLET BOX, STANDARD 609006 (SPECIAL)	EACH	1		1						
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2		2						
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	19300	8512	10788						
61100605	MISCELLANEOUS CONCRETE	CU YD	9.2	5.2	4						
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	3300	1500	1800						
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	1	1						
61139900	STORM SEWERS, SPECIAL 6"	FOOT	500	300	200						

* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -6
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/14/2006 CHECKED BY JAD

LAYOUT	CLC	04/28/06
DRAWN	CLC	04/28/06
REVIEWED	JAD/AMW	04/28/06

12/14/2006
D:\05_Jobs\05e2002\dgn\User\vc60sq.dgn

© Copyright Hanson Professional Services Inc. 2006

HANSON