

SUMMARY OF QUANTITIES

FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		STRUCTURE						
				MACARTHUR EXTENSION CITY SECTION 02-00382-02-PV STA. 798+08.49 TO STA. 876+31.00	MACARTHUR EXTENSION & I-72 INTERCHANGE	MACARTHUR EXTENSION OVER N.S. RAILROAD (S.N. 084-0512)	INTERURBAN TRAIL OVER N.S. RAILROAD (S.N. 084-7008)	MACARTHUR EXTENSION OVER INTERURBAN TRAIL (S.N. 084-7009)	MACARTHUR EXTENSION OVER I-72 (S.N. 084-0513)	I-72 INTERCHANGE RAMP B & C OVER U.P. RAILROAD (S.N. 084-0514 EB, S.N. 084-0516)	I-72 EB & NB OVER U.P. RAILROAD (S.N. 084-0074 EB, S.N. 084-0075 NB)	
				FUNDING - IM 50% STATE / 50% CITY	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE	FUNDING - IM 90% FED / 10% STATE
				CO00	CO00	X181-5B	X932-5B	X92B-2A	X781-2A	X171-5B	X171-5B	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4							
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	29							29		
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	545							545		
81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	46							46		
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACH TO <i>STRUCTURE,</i> 12"X12"X6"	EACH	4							4		
81300980	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8" X 8" X 6"	EACH	1	1								
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	29							29		
X0301699	STORM SEWER JACKED IN PLACE SPECIAL	FOOT	148	148								
X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	2290				2290					
X0323665	RIPRAP SLURRY	SQ YD	4364	264	4100							
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	7							3	4	
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	187								187	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	437							437		
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	33								33	
X0325607	GROUND STABILIZATION GEOSYNTHETIC	SQ YD	5050	2700	2350							
X0325608	GEOSYNTHETIC REINFORCEMENT	SQ YD	10133		10133							
X0325609	TRENCHLESS PIPE INSTALLATION, 72"	FOOT	348		348							
X0325611	PEDESTRIAN UNDERPASS LUMINAIRE	EACH	30	30								
X0325612	CLEARING-SOUTHWEST RECYCLING FACILITY	L SUM	1	1								
X2020500	EARTH EXCAVATION (ROCKFILL)	CU YD	1600		1600							
X5051401	FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 1	L SUM	1								1	
X5051402	FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 2	L SUM	1								1	
X5051403	FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 3	L SUM	1							1		
X5051404	FURNISHING AND ERECTING STRUCTURAL STEEL BRIDGE NO. 4	L SUM	1							1		
XX001176	BITUMINOUS MIXTURE COMPLETE (SPECIAL)	TON	28		28							
XX004350	TRANSVERSE DRAINS COMPLETE	EACH	2		2							
XX005060	PREFABRICATED VERTICAL WICK DRAINS	FOOT	16996	6995	10006							

* PAY ITEM REQUIRES A SPECIAL PROVISION

① 100% CITY

** SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES -8
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

VERT. SCALE:
HORIZ. SCALE:
DATE 12/14/2006
DRAWN BY CLG
CHECKED BY JAD



© Copyright Hanson Professional Services Inc. 2006

12/14/2006
1096/028/06/0222/02/01/028/06/60366/02/01/028/06

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JOU/FAM	04/28/06