

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	43
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

EROSION CONTROL SCHEDULE

LOCATION	HEAVY DUTY EXCELSIOR BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	STONE RIPRAP, CLASS B3	STONE RIPRAP, CLASS B5	STONE DUMPED RIPRAP, CLASS B5	FILTER FABRIC	RIPRAP SLURRY	
	SQ YD	POUND	EACH	FOOT	EACH	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
BEGIN STATION	END STATION / OFFSET										
	44+84.00 RT				1						
	46+50.00 RT				1						
	50+98.50 RT				1						
	SUBTOTAL	2263	13	256	4	871				871	
RAMP D											
	40+00.00 54+00.00 LT AND RT		9								
	41+88.00 49.00 RT					6				6	
	42+25.00 67+47.80 RT			2554							
	44+00.00 56.75 LT					6				6	
	46+98.40 RT					63				63	
	46+98.40 LT					63				63	
	54+00.00 67+51.60 RT		9								
	56+25.00 35.00 RT					6				6	
	52+00.00 RT				1						
	SUBTOTAL		18	2554	1	144				144	
RAMP A INFIELD											
	100+00.00 108+50.00 CL		2								
	101+88.00 107+11.00 LT AND RT	347									
	AREA TOTAL			625							
	SUBTOTAL	347		625	2						
RAMP B INFIELD											
	AREA TOTAL			1050							
	SUBTOTAL			1050							
RAMP C INFIELD											
	AREA TOTAL			400							
	SUBTOTAL			400							
RAMP D INFIELD											
	AREA TOTAL			500	5						
	SUBTOTAL			500	5						
BORROW AREA											
	10+50.00 RT							1409	1550		
	11+60.00 12+05.00 RT		2								
	23+25.00 26+10.00 LT AND RT			900	1						
	SUBTOTAL		2	900	1			1409	1550		
STORM SEWER											
	407+90.00							67	69		
	SUBTOTAL							67	69		
MACARTHUR STORM SEWER											
	99+68.50 BL						176		193		
	108+62.40 BL				1						
	111+42.00 BL				1						
	SUBTOTAL				2		176		193		
RECREATION DRIVE											
	100+00.00 117+50.00 LT AND RT		12								
	100+95.00 106+60.00 LT			636							
	101+30.00 RT					6				6	
	101+62.00 LT					6				6	
	104+20.00 LT					13				13	
	105+50.00 109+50.00 RT			377							
	115+00.00 RT										
	115+00.00 LT										
	117+50.00 128+00.00 LT AND RT		6								
	124+00.00 126+00.00 LT			163							
	124+75.00 125+25.00 LT					70				70	
	124+75.00 125+30.00 RT					75				75	
	104+20.00 RT										
	125+22.80 LT										
	126+45.00 LT										
	SUBTOTAL		18	1176	5	170				170	
LINCOLNSHIRE BOULEVARD											
	180+00.00 182+00.00 LT AND RT		2								
	180+70.70 183+77.20 RT			334							
	182+00.00 184+00.00 LT AND RT		2								
	SUBTOTAL		4	334							
WEST GRAND AVENUE											
	182+10.00 183+75.00 LT AND RT				4						
	SUBTOTAL				4						
CENTRE STREET											
	10+60.00 13+30.00 LT			286	1						
	10+60.00 13+30.00 RT			301							
	SUBTOTAL			586	1						
INTERURBAN TRAIL PARKING LOT											
	SUBTOTAL				2						
	TOTAL	3614	5700	190	10750	77	4364	599	1409	2128	4364

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -7
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY MH
 DATE 05/20/2005



12/16/2006 \$FILES
 LAYOUT CLG 05/ / 05
 DRAWN CLG 05/ / 05
 REVIEWED JMO/JMH 05/ / 05