

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

REMOVAL SCHEDULE

LOCATION	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	APPROACH SLAB REMOVAL	BITUMINOUS CONCRETE SHOULDER REMOVAL	PAVED DITCH REMOVAL	PAVEMENT REMOVAL (SPECIAL)	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 24"	REMOVING INLETS	GUARDRAIL REMOVAL	FILLING EXISTING CULVERTS
	ACRE	SQ YD	FOOT	SQ YD	SQ YD	FOOT	SQ YD	EACH	FOOT	FOOT	EACH	FOOT	EACH
BEGIN END STATION / STATION OFFSET OFFSET													
MACARTHUR BOULEVARD													
790+25.00 95' RT								1					1
790+70.00 90' RT													
791+30.00 80' RT								1					
791+47.00 78' RT								1					
792+10.00 70' RT													1
792+62.00 68' RT								1					
797+50.00 30' LT									24				
839+30.00 844+60.00 LT & RT		589											
840+10.00 841+30.00 RT										150			
841+34.00 40' RT												12	
873+75.35 876+81.00 LT		686											
876+13.00 876+31.00			18										
MACARTHUR AT ABANDONED RR	1.25												
MACARTHUR AT JUNCTION CIRCLE AND CUL DE SAC	0.75												
MACARTHUR AT NS	1.25												
MACARTHUR AT WEST GRAND	0.75												
SUBTOTAL	4.00	1275	18					4	24	150		12	2
INTERSTATE 72													
582+00.00 78' RT								1					
582+00.00 78' RT										8			
591+74.00 607+07.00 RT					1703								
591+74.00 607+19.00 RT					1030								
592+00.00 88' LT								1					
592+00.00 90' RT								1					
597+57.10 607+18.21 RT												965	
600+64.50 607+66.00 LT												702	
605+20.00 607+66.00 LT					273								
605+20.00 607+53.00 LT					155								
605+70.00 607+19.00 RT												178	
606+52.00 607+00.00 RT						45							
607+16.00 92' LT								1					1
607+16.00 63' LT											1		
609+35.00 618+06.00 RT												871	
609+35.00 611+90.00 RT					283								
609+50.00 611+60.00 RT					140								
609+53.00 610+31.00 RT						65							
609+89.00 611+40.00 LT												175	
609+89.00 625+30.00 LT													960
610+06.00 619+65.60 LT					1027								
610+06.00 625+50.30 LT					1716								
610+60.00 88' LT								1					1
610+60.00 63' LT											1		
INTERURBAN TRAIL BENEATH BRIDGE OVER UPRR		75											
EASTBOUND BRIDGE, EAST APPROACH				139									
EASTBOUND BRIDGE, WEST APPROACH				139									
WESTBOUND BRIDGE, EAST APPROACH				141									
WESTBOUND BRIDGE, WEST APPROACH				139									
SUBTOTAL		75		557	6329	110		5		8	2	3851	2
RAMP A													
15+81.00 16' LT								1					
23+71.00 88' LT										37			
SUBTOTAL								1		37			
RAMP B													
27+12.00 50' LT										42			
28+30.00 128' LT										68			
31+72.00 41' LT								1					1
33+41.73 69.09' LT								1					
35+32.00 LT TO RAMP C 45+50.00 RT							2169						
35+20.31 19.67' LT								1					
35+63.92 65.01' LT								1					
INTERURBAN TRAIL BENEATH BRIDGE OVER UPRR		36											
SUBTOTAL		36						2169	4	110			1

© Copyright Hanson Professional Services Inc. 2003



12/16/2006 \$FILES
 LAYOUT CLG 05/ / 05
 DRAWN CLG 05/ / 05
 REVIEWED JMD/JMD 05/ / 05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -9
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY MH
 DATE 05/20/2005