

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

SEEDING SCHEDULE

LOCATION	SEEDING, CLASS 2	SEEDING, CLASS 3	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MOWING	MULCH, METHOD 2	SUPPLEMENTAL WATERING
	ACRE	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	ACRE	UNIT
BEGIN STATION END STATION OFFSET										
MACARTHUR BOULEVARD										
26+50.00 784+00.00 (RAMP A/MAC)		1.50		135	135	135	3.0			1.50
34+00.00 798+08.49 (RAMP C/MAC)		4.75		428	428	428	9.5			4.75
789+60.00 784+00.00	5.00			450	450	450	10.0	5.00		5.00
784+00.00 44+00.00 (MAC/RAMP B)		7.25		653	653	653	14.5			7.25
798+08.49 48+00.00 (MAC/RAMP D)		1.50		135	135	135	3.0			1.50
PARKING LOT										
798+08.49 809+00.00	0.25			23	23	23	1.5	0.25		0.25
809+00.00 820+75.00	4.75			563	563	563	12.5			6.25
820+75.00 820+95.19	0.25			428	428	428	9.5	4.75		4.75
820+95.19 839+27.20	4.25			23	23	23	0.5	0.25		0.25
839+27.20 865+50.00	5.25			383	383	383	8.5	4.25		4.25
865+50.00 877+36.80	2.25			473	473	473	10.5	5.25		5.25
MEDIAN										
				203	203	203	4.5	2.25		2.25
				105	105	105	3.5			
	SUBTOTAL	22.00	21.25	3998	3998	3998	91.0	22.00	43.25	
RAMP A										
10+00.00 26+50.00 RT	2.00			180	180	180	4.0	2.00		2.00
	SUBTOTAL	2.00		180	180	180	4.0	2.00	2.00	
RAMP B										
44+00.00 50+41.36 RT	1.25			113	113	113	2.5	1.25		1.25
	SUBTOTAL	1.25		113	113	113	2.5	1.25	1.25	
RAMP C										
30+00.00 34+00.00 RT	0.75			68	68	68	1.5	0.75		0.75
38+50.00 42+50.00 RT										80.00
	SUBTOTAL	0.75		68	68	68	1.5	0.75	0.75	80.00
RAMP D										
48+00.00 67+51.59 RT	7.00			630	630	630	14.0	7.00		7.00
	SUBTOTAL	7.00		630	630	630	14.0	7.00	7.00	
INFIELD AREA A										
RAMP A INFIELD	5.00	1.25		563	563	563	12.5	5.00		6.25
	SUBTOTAL	5.00	1.25	563	563	563	12.5	5.00	6.25	
INFIELD AREA B										
RAMP B INFIELD	7.25	3.25		945	945	945	21.0	7.25		10.50
	SUBTOTAL	7.25	3.25	945	945	945	21.0	7.25	10.50	
INFIELD AREA C										
RAMP C INFIELD	1.75	2.25		360	360	360	8.0	1.75		4.00
	SUBTOTAL	1.75	2.25	360	360	360	8.0	1.75	4.00	
INFIELD AREA D										
RAMP D INFIELD	3.25	1.75		450	450	450	10.0	3.25		5.00
	SUBTOTAL	3.25	1.75	450	450	450	10.0	3.25	5.00	
RECREATION DRIVE										
ROADWAY TOTAL	5.00			450	450	450	10.0	5.00		5.00
	SUBTOTAL	5.00		450	450	450	10.0	5.00	5.00	
BORROW AREA										
400+00.00 407+89.00 STORM SEWER	1.00			90	90	90	2.0	1.00		1.00
AREA TOTAL	3.00			270	270	270	6.0	3.00		3.00
	SUBTOTAL	4.00		360	360	360	8.0	4.00	4.00	
LINCOLNSHIRE BOULEVARD										
ROADWAY TOTAL	0.50			45	45	45	1.0	0.50		0.50
	SUBTOTAL	0.50		45	45	45	1.0	0.50	0.50	
CENTRE STREET										
ROADWAY TOTAL	0.25			23	23	23	0.5	0.25		0.25
	SUBTOTAL	0.25		23	23	23	0.5	0.25	0.25	
INTERURBAN TRAIL										
ROADWAY TOTAL	1.25			113	113	113	2.5	1.25		1.25
	SUBTOTAL	1.25		113	113	113	2.5	1.25	1.25	
PROJECT TOTAL										
CITY SECTION NORTH OF STATION 798+08.49			51.50							
STATE SECTION SOUTH OF STATION 798+08.49			130.50							
			182							
	TOTAL	61.25	29.75	182	8296	8296	186.5	61.25	91.00	80.00

© Copyright Hanson Professional Services Inc. 2003



12/16/2006 \$FILES
 LAYOUT CLG 05/ / 05
 DRAWN CLG 05/ / 05
 REVIEWED JMD/JMK 05/ / 05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES -11
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY MH
 DATE 05/20/2005