CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	49
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 # 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 2

						INLETS													MANHOLES										REINF. CONC. PIPE TEE																			
(NO.)	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	COMMENTS
45	MAC BLVD	798+00.00	15.80	L	641.43		1																																										
46	MAC BLVD	798+00.00	59.00	L	640.50						1																																						
47	MAC BLVD	798+00.00	105.00	L	619.50																																		1							18		
48	MAC BLVD	798+00.00	15.80	R	641.43		1																																										
49	MAC BLVD	798+00.00	53.00	R	640.50													1																															
50	MAC BLVD	798+00.00	120.00	R	619.50																																		1							18		
51	N/A																																																
52	MAC SS	108+63.00	0.0		600.50																				1												1											
53	MAC SS	111+89.45	0.0		598.50																				1												1											
54	N/A																																																
55	MAC BLVD	799+10.00	13.54	L	640.44		1																																										
56	MAC BLVD	799+06.00	56.92	L	639.65						1																																						
57	MAC BLVD	798+90.00	146.00	L	602.50																																		1							18		
58	MAC BLVD	799+27.00	13.17	R	640.25		1																																										
59	MAC BLVD	799+69.50	49.58	R	639.02											1																																	
60	MAC BLVD	799+69.50	160.00	R	599.66																																		1							18		
61	MAC BLVD	801+66.00	56.92	L	635.50										1																																		
62	MAC BLVD	801+66.00	140.00	L	598.84																																		1							18		
63	N/A																																																
64	N/A																																																
65	MAC BLVD	802+30.00	49.58	R	634.40										1																																		
66	MAC BLVD	802+70.00	155.00	R	600.00																																		1							18		
67	MAC BLVD	807+00.00	56.50	L	624.87												1																																
68	MAC BLVD	807+00.00	129.40	L	597.50																	1																	1									
69	MAC BLVD	807+00.00	7.30	L	626.04		1																																										
70	MAC BLVD	807+00.00	7.30	R	626.04		1																																										
71	MAC BLVD	807+00.00	48.50	R	625.03													1																															
72	MAC BLVD	807+00.00	164.90	R	597.50																							1											1									
73	MAC BLVD	812+00.00	58.90	L	615.07												1																																
74	MAC BLVD	812+00.00	137.20	L	597.50																	1																	1									
75	MAC BLVD	812+00.00	7.30	L	616.29		1																																										
76	MAC BLVD	812+00.00	7.30	R	616.29		1																																										
77	MAC BLVD	812+00.00	58.90	R	615.07													1																															
78	MAC BLVD	812+00.00	135.40	R	597.50																					1													1									
79	MAC BLVD	817+00.00	62.50	L	605.39												1																																
80	MAC BLVD	817+00.00	96.00	L	598.97																	1																	1									
81	MAC BLVD	817+00.00	7.30	L	606.69		1																																										
82	MAC BLVD	817+00.00	7.30	R	606.69		1																																										
83	MAC BLVD	817+00.00	68.50	R	605.27													1																															
84	MAC BLVD	817+00.00	100.00	R	598.97																					1													1									
85	N/A																																																
86	N/A																																																
87	N/A																																																
88	N/A																																																

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -2
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/18/2006 CHECKED BY JWM

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JWM	04/28/06

12/18/2006
#72541

© Copyright Hanson Professional Services Inc. 2006

HANSON