CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	52
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 # 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 5

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS														MANHOLES											REINF. CONC. PIPE TEE																		COMMENTS
						TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER.	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	
177	MAC BLVD	849+40.00	58.20	L	606.52		1																																										
178	MAC BLVD	849+40.00	7.30	L	607.45		1																																										
179	MAC BLVD	849+40.00	7.30	R	607.45		1																																										
180	MAC BLVD	849+40.00	46.20	R	606.76		1																																										
181	MAC BLVD	849+40.00	64.35	R	"T"																															1													
182	MAC BLVD	850+95.00	58.20	L	606.05				1																																								
183	MAC BLVD	850+95.00	x	L	x				1																																								
184	MAC BLVD	850+95.00	x	L	x				1																																								
185	MAC BLVD	850+95.00	46.20	R	606.29				1																																								
186	MAC BLVD	850+95.00	64.20	R	603.25																								1											1									
187	MAC BLVD	850+95.00	90.30	L	603.25					1																																							
188	N/A																																																
189	N/A																																																
190	N/A																																																
191	N/A																																																
192	N/A																																																
193	MAC BLVD	854+05.00	58.20	L	605.12		1																																										
194	MAC BLVD	854+05.00	7.30	L	606.05		1																																										
195	MAC BLVD	854+05.00	7.30	R	606.05		1																																										
196	MAC BLVD	854+05.00	46.20	R	605.36		1																																										
197	MAC BLVD	854+05.00	63.50	R	"T"																															1													
198	MAC BLVD	855+60.00	58.20	L	604.66		1																																										
199	MAC BLVD	855+60.00	7.30	L	605.59		1																																										
200	MAC BLVD	855+60.00	7.30	R	605.59		1																																										
201	MAC BLVD	855+60.00	46.20	R	604.90		1																																										
202	MAC BLVD	855+60.00	63.15	R	"T"																															1													
203	MAC BLVD	857+15.00	69.50	L	601.54					1																																							
204	MAC BLVD	857+15.00	51.30	L	604.33				1																																								
205	MAC BLVD	857+15.00	7.30	L	605.12				1																																								
206	MAC BLVD	857+15.00	7.30	R	605.12				1																																								
207	MAC BLVD	857+15.00	46.20	R	604.43				1																																								
208	MAC BLVD	857+15.00	62.80	R	601.54																			1																1									
209	MAC BLVD	858+10.00	46.20	L	604.15		1																																										
210	MAC BLVD	858+10.00	7.30	L	604.84		1																																										
211	MAC BLVD	858+10.00	7.30	R	604.84		1																																										
212	MAC BLVD	858+10.00	46.20	R	604.15		1																																										
213	MAC BLVD	858+10.00	63.95	R	"T"																													1															
214	MAC BLVD	858+90.00	46.20	L	603.95		1																																										
215	MAC BLVD	858+90.00	46.20	R	603.95		1																																										
216	MAC BLVD	859+00.00	46.20	L	603.95				1																																								
217	MAC BLVD	859+00.00	46.20	R	603.95				1																																								
218	MAC BLVD	859+00.00	65.10	R	"T"																													1															
219	MAC BLVD	859+70.00	46.20	L	604.10		1																																										
220	MAC BLVD	859+70.00	46.20	R	604.10		1																																										

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -5
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. | DRAWN BY CLC
DATE 12/18/2006 | CHECKED BY JWM

© Copyright Hanson Professional Services Inc. 2006

HANSON

12/18/2006
#FILE#

LAYOUT	CLC	04/28/06
DRAWN	CLC	04/28/06
REVIEWED	JWJ/JWM	04/28/06