CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	53
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 6

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	COMMENTS
221	MAC BLVD	859+70.00	66.25	R	"T"																											1																	
222	MAC BLVD	861+00.00	69.40	L	600.50					1																																							
223	MAC BLVD	861+00.00	40.20	L	604.64				1																																								
224	MAC BLVD	861+00.00	40.20	R	604.64				1																													1											
225	MAC BLVD	861+00.00	67.40	R	600.50																			1																									
226	MAC BLVD	862+30.00	34.20	L	605.17		1																																										
227	MAC BLVD	862+30.00	34.20	R	605.17		1																																										
228	MAC BLVD	862+30.00	64.60	R	"T"																											1																	
229	MAC BLVD	865+60.00	38.24	L	605.15				1																																								
230	MAC BLVD	865+60.00	34.20	R	605.23				1																																								
231	MAC BLVD	865+60.00	59.00	R	600.90																			1														1											
232	MAC BLVD	868+00.00	57.00	L	600.00																																		1								18		
233	MAC BLVD	868+00.00	34.20	L	604.50				1																																								
234	MAC BLVD	868+00.00	34.20	R	604.50				1																																								
235	MAC BLVD	868+00.00	41.00	R	604.40																			1												1													
236	MAC BLVD	866+80.00	34.20	R	604.87		1																																										
237	MAC BLVD	866+80.00	49.00	R	"T"																										1																		
238	MAC BLVD	869+50.00	34.20	L	604.05		1																																										
239	MAC BLVD	869+50.00	34.20	R	604.05		1																																										
240	MAC BLVD	869+50.00	41.00	R	"T"																										1																		
241	MAC BLVD	871+00.00	54.00	L	600.63					1																																							
242	MAC BLVD	871+00.00	34.20	L	603.59				1																																								
243	MAC BLVD	871+00.00	34.20	R	603.59				1																																								
244	MAC BLVD	871+00.00	41.00	R	603.50																			1												1													
245	MAC BLVD	871+90.00	34.20	L	603.37		1																																										
246	MAC BLVD	871+90.00	34.20	R	603.37		1																																										
247	MAC BLVD	872+00.00	34.20	L	603.37				1																																								
248	MAC BLVD	872+00.00	34.20	R	603.37				1																																								
249	MAC BLVD	872+00.00	41.00	R	"T"																									1																			
250	MAC BLVD	873+50.00	32.10	L	603.98		1																																										
251	MAC BLVD	873+50.00	35.10	R	603.98		1																																										
252	MAC BLVD	873+50.00	47.00	R	"T"																									1																			
253	MAC BLVD	875+10.00	30.70	L	604.95																		1														1												
254	MAC BLVD	875+10.00	38.44	R	604.79																		1														1												
255	MAC BLVD	875+10.00	65.00	R	602.26																		1																1									
256	CENTRE ST	10+70.00	14.70	L	602.31				1																																								
257	CENTRE ST	10+70.00	14.70	R	602.31				1																																								
258	CENTRE ST	13+00.00	17.60	L	604.05		1																																										
259	CENTRE ST	13+00.00	14.70	R	604.11																1																						1				18		
260	RAMP A	10+00.00	25.00	R	598.00																																						1				18		
261	RAMP A	18+00.00	45.00	R	594.50																																												
262	MAC BLVD	874+32.10	75.43	L	603.13		1																																										
263	MAC BLVD	875+20.00	63.20	L	602.00			1																																									
264	RAMP A	15+81.00	21.98	L	601.82	1																																											

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -6
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/18/2006 CHECKED BY JMM

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVISED	JMD/JNM	04/28/06

12/18/2006
#FILE#

© Copyright Hanson Professional Services Inc. 2006
HANSON