CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	56
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 9

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS													MANHOLES										REINF. CONC. PIPE TEE																		COMMENTS
						TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	G&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	
353	RAMP C	53+50.00	20.00	R	632.90												1																														
354	RAMP C	53+50.00	122.00	R	599.34																																		1							18	
355	RAMP C	53+50.00	33.43	L	633.65						1																																				
356	RAMP C	53+50.00	72.50	L	616.67																																		1							18	
357	RAMP D	44+00.00	22.00	L	632.38						1																																				
358	RAMP D	44+00.00	56.75	L	616.50																																		1							18	
359	RAMP D	46+98.40	20.00	L	621.76																																										
360	RAMP D	46+98.40	41.25	L	614.00																																		1							18	
361	RAMP A	12+00.00	16.50	R	600.27															1																											
362	RAMP A	14+20.00	16.50	R	599.76															1																											
363	MAC BLVD	859+00.00	7.30	L	604.64		1																																								
364	MAC BLVD	859+00.00	7.30	R	604.64		1																																								
365	MAC BLVD	859+70.00	7.30	L	604.79		1																																								
366	MAC BLVD	859+70.00	7.30	R	604.79		1																																								
367	MAC BLVD	861+00.00	7.30	L	605.21				1																																						
368	MAC BLVD	861+00.00	7.30	R	605.21				1																																						
369	MAC BLVD	862+30.00	7.30	L	605.62		1																																								
370	MAC BLVD	862+30.00	7.30	R	605.62		1																																								
371	MAC BLVD	865+60.00	7.30	L	605.68				1																																						
372	MAC BLVD	869+50.00	7.30	R	604.50		1																																								
373	MAC BLVD	871+00.00	7.30	L	604.04				1																																						
374	MAC BLVD	871+00.00	7.30	R	604.04				1																																						
375	MAC BLVD	872+00.00	7.30	L	603.82		1																																								
376	MAC BLVD	872+00.00	7.30	R	603.82		1																																								
377	I 72	607+56.00	69.03	L	631.92										1																																
378	I 72	607+56.00	110.00	L	624.90																																		1							18	
379	I 72	610+34.50	69.00	L	631.95										1																																
380	RAMP C	44+65.00	38.00	L	630.00					1																																					
381	I 72	607+00.50	28.96	R	631.81								1																																		
382	I 72	607+00.50	17.00	R	630.60																																		1							18	
383	I 72	609+69.00	29.00	R	632.23								1																																		
384	I 72	610+24.00	12.00	R	629.50																																		1							18	
385	RAMP B	36+50.00	35.00	L	630.00			1																																							
386	RAMP B	36+50.00	52.50	R	612.29																																		1							18	
387	STM SEWER	404+00.00	0.0		597.60																			1											1												
388	RAMP C	51+43.00	29.70	L	631.92		1																																								
389	RAMP C	51+43.00	66.00	L	597.50																																		1							18	
390	MAC BLVD	837+20.00	120.00	L	604.89					1																																					
391	MAC BLVD	832+25.00	165.00	L	603.43					1																																					
392	MAC BLVD	824+00.00	140.00	L	601.10					1																																					
393	MAC BLVD	817+00.00	164.00	L	599.00					1																																					
394	MAC BLVD	812+00.00	206.00	L	597.50					1																																					
395	MAC SS	116+49.00	0.0		611.00																					1									1												
396	MAC SS	114+79.00	0.0		601.00																					1									1												

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -9
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. DRAWN BY CLG
DATE 12/18/2006 CHECKED BY JWM

LAYOUT	C.L.G.	04/28/06
DRAWN	C.L.G.	04/28/06
REVIEWED	JJD/JWM	04/28/06

12/18/2006
$FILE$

HANSON

© Copyright Hanson Professional Services Inc. 2006