CONTRACT #72541

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	58
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV

DRAINAGE STRUCTURE SCHEDULE – 11

NO.	ROADWAY	STATION	OFFSET FEET		FRAME ELEV	INLETS: TYPE A, T1 F&L (OPEN)	TYPE A, T3 F&G	TYPE A, T37G	TYPE B, T3 F&G	TYPE B, T37G	TYPE B, STD 609006	TYPE B, STD 609006 SPCL	TYPE C, STD 609006	TYPE C, STD 609006 SPCL	TYPE D, STD 609006	TYPE D, STD 609006 SPCL	TYPE E, STD 610001	TYPE F, STD 610001	TYPE F, STD 610001 SPCIL	MANHOLES: TYPE A, 4' DIA T1 CL	TYPE A, 4' DIA T8G	TYPE A, 4' DIA T3 F&G	TYPE A, 4' DIA	TYPE A, 5' DIA	TYPE A, 6' DIA	SPECIAL TYPE 1	SPECIAL TYPE 2	SPECIAL TYPE 3	SPECIAL TYPE 4	SPECIAL TYPE 5	REINF. CONC. PIPE TEE: 36" PIPE 12" RISER	42" PIPE 12" RISER	48" PIPE 12" RISER	54" PIPE 12" RISER	60" PIPE 12" RISER	66" PIPE 12" RISER	FRAME & LID TY 1 CL	F&G TYPE 3	C&C TYPE 2B	GRATE TYPE 37	12" PRC FLARED END SECTION	18" PRC FLARED END SECTION	24" PRC FLARED END SECTION	36" PRC FLARED END SECTION	72" PRC FLARED END SECTION	GRATING FOR END SECTION 24"	MH TO BE RECONSTRUCTED	HEAVY DUTY EXCELSIOR BLANKET	COMMENTS
441	MAC BLVD	831+00.00	x	R	x		1																																								
442	MAC BLVD	831+00.00	52.20	R	607.05		1																																								
443	MAC BLVD	831+00.00	73.75	R	"T"																													1													
444	MAC BLVD	834+00.00	64.20	L	607.83		1																																								
445	MAC BLVD	834+00.00	7.30	L	608.88		1																																								
446	MAC BLVD	834+00.00	7.30	R	608.88		1																																								
447	MAC BLVD	834+00.00	52.20	R	608.07		1																																								
448	MAC BLVD	834+00.00	72.75	R	"T"																													1													
449	MAC BLVD	834+75.00	64.20	L	608.08		1																																								
450	MAC BLVD	834+75.00	x	L	x		1																																								
451	MAC BLVD	834+75.00	x	R	x		1																																								
452	MAC BLVD	834+75.00	52.20	R	608.32		1																																								
453	MAC BLVD	834+75.00	72.00	R	"T"																													1													
454	MAC BLVD	836+00.00	61.80	L	608.54		1																																								
455	MAC BLVD	836+00.00	7.30	L	609.55		1																																								
456	MAC BLVD	836+00.00	7.30	R	609.55		1																																								
457	MAC BLVD	836+00.00	49.80	R	608.78		1																																								
458	MAC BLVD	836+00.00	71.00	R	"T"																													1													
459	N/A																																															
460	N/A																																															
461	N/A																																															
462	N/A																																															
463	N/A																																															
464	N/A																																															
465	N/A																																															
466	N/A																																															
467	N/A																																															
468	MAC BLVD	842+00.00	65.40	R	"T"																													1													
469	MAC BLVD	804+50.00	56.50	L	629.74													1																													
470	MAC BLVD	804+50.00	85.00	L	615.50																																		1							18	
471	MAC BLVD	804+50.00	44.50	R	629.98													1																													
472	MAC BLVD	804+50.00	92.00	R	615.50																																		1							18	
473	MAC BLVD	809+50.00	56.50	L	619.99													1																													
474	MAC BLVD	809+50.00	140.00	L	598.33																																		1							18	
475	MAC BLVD	809+50.00	53.50	R	620.05													1																													
476	MAC BLVD	809+50.00	135.00	R	598.33																																		1							18	
477	MAC BLVD	814+50.00	62.50	L	610.12													1																													
478	MAC BLVD	814+50.00	118.00	L	598.25																																		1							18	
479	MAC BLVD	814+50.00	64.50	R	610.03													1																													
480	MAC BLVD	814+50.00	118.00	R	598.25																																		1							18	
482	MAC BLVD	844+00.00	90.60	L	605.17																																				1			1			
483	MAC BLVD	844+00.00	58.20	L	608.14				1																																						
484	MAC BLVD	844+00.00	7.30	L	609.07				1																																						
485	MAC BLVD	844+00.00	7.30	R	609.07				1																																						

NOTE:
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DRAINAGE STRUCTURE SCHEDULE -11
FAI-72, MACARTHUR BLVD
SEC NO. 02-00382-02-PV
SEC NO. (84-9-4)A,HBK,BY,BY-1
SANGAMON COUNTY, ILLINOIS

SCALE: VERT. HORIZ. | DRAWN BY CLG
DATE 12/18/2006 | CHECKED BY JWM

© Copyright Hanson Professional Services Inc. 2006

HANSON

12/18/2006
#72E.8

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JWM	04/28/06