

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	60
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

# STORM SEWER SCHEDULE - 1

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A												TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS	
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6						
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"						18"
1	596.77	4	596.37	7																	
2	596.82	3	595.05														14		END SEWER @ TOP OF SLOPE		
4	596.37	5	596.14	35																	
5	595.90	298	595.00														14		END SEWER @ TOP OF SLOPE		
6	590.50	387	588.47				395														
7	603.06	10	602.66	13																	
8	603.02	9	596.80														33		END SEWER @ TOP OF SLOPE		
10	602.66	11	602.19	29																	
11	602.19	12	596.80														32		END SEWER @ TOP OF SLOPE		
13	613.06	16	612.66	13																	
14	613.02	15	598.80														66		END SEWER @ TOP OF SLOPE		
16	612.66	17	612.43	29																	
17	612.19	18	598.80														65		END SEWER @ TOP OF SLOPE		
19	622.66	20	622.43	30																	
20	622.19	21	610.30														28		END SEWER @ TOP OF SLOPE		
22	623.06	19	622.66	29																	
23	623.02	24	610.30														27		END SEWER @ TOP OF SLOPE		
25	623.85	26	610.63														27		END SEWER @ TOP OF SLOPE		
27	623.81	28	610.02														27		END SEWER @ TOP OF SLOPE		
29	628.32	30	611.25														42		END SEWER @ TOP OF SLOPE		
31	628.33	32	611.30														59		END SEWER @ TOP OF SLOPE		
33	635.64	34	602.00														86		END SEWER @ TOP OF SLOPE		
35	635.83	36	600.50														94		END SEWER @ TOP OF SLOPE		
37	638.69	38	600.50														97		END SEWER @ TOP OF SLOPE		
39	638.77	40	603.00														96		END SEWER @ TOP OF SLOPE		
41	635.71	42	618.27														36		END SEWER @ TOP OF SLOPE		
43	636.51	44	618.50														96		END SEWER @ TOP OF SLOPE		
45	637.87	48	637.47	33																	
46	637.83	47	619.50														41		END SEWER @ TOP OF SLOPE		
48	637.47	49	637.24	29																	
49	637.00	50	619.50														60		END SEWER @ TOP OF SLOPE		
52	582.64	53	583.24																		
53	583.24	396	583.79									290			321						
55	636.88	58	636.28	30																	
56	637.65	57	602.50														89		END SEWER @ TOP OF SLOPE		
58	636.28	59	635.76	50																	
59	635.52	60	599.66														108		END SEWER @ TOP OF SLOPE		
61	633.50	62	598.84														83		END SEWER @ TOP OF SLOPE		
65	632.40	66	600.00														103		END SEWER @ TOP OF SLOPE		
67	622.20	68	595.50														74		END SEWER @ TOP OF SLOPE		
68	593.00	72	591.00												293		30		END SEWER @ TOP OF SLOPE		
69	622.48	70	622.08	13																	
70	622.08	71	621.77	29																	
71	621.53	72	595.50														116		END SEWER @ TOP OF SLOPE		
72	584.91	78	585.84											496							
73	612.40	74	595.50														75		END SEWER @ TOP OF SLOPE		

NOTE:  
SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
STORM SEWER SCHEDULE -1  
FAI-72, MACARTHUR BLVD  
SEC NO. 02-00382-02-PV  
SEC NO. (84-9-4)A,HBK,BY,BY-1  
SANGAMON COUNTY, ILLINOIS

SCALE: VERT.      DRAWN BY    CLG  
          HORIZ.      CHECKED BY   JWM  
DATE: 12/18/2006



© Copyright Hanson Professional Services Inc. 2006  
12/18/2006  
\$FILES  
LAYOUT    CLG    04/28/06  
DRAWN     CLG    04/28/06  
REVIEWED JWB/JWM 04/28/06