

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	61
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

# STORM SEWER SCHEDULE - 2

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A														TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS						
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6													
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"	18"	72"											
74	593.00	78	587.84																270									
75	612.73	76	612.33	13																								
76	612.33	77	611.81	29																								
77	611.57	78	595.50																									
78	585.84	84	586.77							498														74		END SEWER @ TOP OF SLOPE		
79	602.72	80	596.97																									
80	594.47	84	588.77					193																	29	102	END SEWER @ TOP OF SLOPE	
81	603.12	82	602.72	13																								
82	602.72	83	602.01	29																								
83	601.77	84	596.97																								27	END SEWER @ TOP OF SLOPE
84	586.77	414	587.32									302																
100	598.10	101	597.85					18																				
101	597.85	102	597.35					75																				
102	597.35	103	597.05					36																				
103	597.05	104	596.50					18																				
104	588.07	418	587.89																									
127	600.43	128	600.18					19																				
128	600.18	129	599.88					45																				
129	599.88	130	599.68					4																				
130	599.68	131	599.38					59																				
131	599.38	132	598.46					19																				
132	589.60	443	589.37																									
143	601.89	144	601.64					21							117													
144	601.64	145	601.34					49																				
145	601.34	146	601.14					12																				
146	601.14	147	600.84					37																				
147	600.84	148	600.64					21																				
148	590.52	458	590.30												112													
149	###	150	###	25																								
150	###	151	###	13																								
151	###	152	###	25																								
152	605.46	153	593.20	19																								
153	591.20	148	590.52												348													END SEWER @ TOP OF SLOPE
156	###	157	###																									
157	###	158	###																									
158	###	159	###																									
159	605.10	468	593.42	18																								END SEWER @ TOP OF SLOPE
161	605.28	162	604.98	25																								
162	604.98	163	604.78	13																								
163	604.78	164	604.28	25																								
164	604.28	165	593.68	17																								END SEWER @ TOP OF SLOPE
165	591.93	487	591.79												71													
166	604.81	167	604.51	25																								
167	604.51	168	604.31	13																								
168	604.31	169	603.81	25																								
169	603.81	170	593.96	16																								END SEWER @ TOP OF SLOPE

NOTE:  
 SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT  
 CONSTRUCTED IN GRADING & STRUCTURES CONTRACT.  
 SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 STORM SEWER SCHEDULE -2  
 FAI-72, MACARTHUR BLVD  
 SEC NO. 02-00382-02-PV  
 SEC NO. (84-9-4)A,HBK,BY,BY-1  
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT.      DRAWN BY CLG  
 HORIZ.              CHECKED BY JWM  
 DATE 12/18/2006



12/18/2006  
 \$FILES  
 LAYOUT CLG 04/28/06  
 DRAWN CLG 04/28/06  
 REVIEWED JWB/JWM 04/28/06