

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	63
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

STORM SEWER SCHEDULE - 4

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A													TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6						
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"	18"					
220	600.22	221	596.21	15															END SEWER @ TOP OF SLOPE		
221	594.71	225	594.95						124												
222	597.50	223	597.30		27																
223	597.30	367	597.00		30													25			
224	596.50	225	595.95		23																
225	594.95	228	595.19						125												
226	602.06	369	601.76	25																	
227	601.26	228	596.69	25															END SEWER @ TOP OF SLOPE		
228	595.19	231	595.81						324												
229	596.58	371	596.36		28													30			
230	596.01	231	595.81		21																
231	595.81	237	596.03					115													
232	600.00	233	599.80		16																
233	599.80	234	599.00		66													15			
234	599.00	235	598.25		3																
235	596.25	240	596.53						153												
236	601.26	237	597.28	10															END SEWER @ TOP OF SLOPE		
237	596.03	235	596.25						116												
238	600.93	372	600.43	40															END SEWER @ TOP OF SLOPE		
239	600.13	240	597.78	3																	
240	596.53	244	596.81						153												
241	597.63	242	597.43		17																
242	597.43	373	597.28		24													10			
243	597.03	244	596.81		3																
244	596.81	249	597.00				100														
245	600.35	247	600.25	8																	
246	600.35	248	599.45	8																	
247	600.25	375	599.95	25																	
248	599.45	249	598.00	2															END SEWER @ TOP OF SLOPE		
249	597.00	252	597.28				145														
250	600.86	251	600.06	65															END SEWER @ TOP OF SLOPE		
251	600.06	252	598.28	7																	
252	597.28	255	597.57				155														
253	598.30	254	597.70				65											40			
254	597.70	255	597.57				12														
256	598.73	257	598.43	27														3			
257	598.43	259	597.33	227														65			
258	600.93	259	600.63	29														2			
259	597.33	299	596.83		51																
260	598.00	361	596.44				193														
262	599.92	253	598.30	90																	
263	600.58	253	600.28	31																	
264	595.72	265	594.47	38														11	END SEWER @ 264		
265	594.47	261	594.50				210														
266	627.96	267	614.14															61	END SEWER @ TOP OF SLOPE		
268	614.83	269	600.76															60	END SEWER @ 268		

NOTE:
 SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT
 CONSTRUCTED IN GRADING & STRUCTURES CONTRACT.
 SHOWN FOR INFORMATION ONLY.

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -4
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. _____
 HORIZ. _____
 DATE 12/18/2006

DRAWN BY CLG
 CHECKED BY JWM



© Copyright Hanson Professional Services Inc. 2006
 12/18/2006
 \$FILES
 LAYOUT CLG 04/28/06
 DRAWN CLG 04/28/06
 REVIEWED JWM/JWM 04/28/06