

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	65
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

STORM SEWER SCHEDULE - 6

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A													TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6						
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"	18"					
362	595.78	399	595.60			76															
363	600.78	364	600.58	13																	
364	600.58	217	600.58	25																	
365	600.92	366	600.72	13																	
366	600.72	220	600.22	25																	
367	597.00	368	596.80		12													11			
368	596.80	224	596.50		30													28			
369	601.76	370	601.56	13																	
370	601.56	227	601.26	25																	
371	596.36	230	596.01		39													44			
372	600.43	239	600.13	25																	
373	597.28	374	597.18		12													8			
374	597.18	243	597.03		24													16			
375	599.95	376	599.75	13																	
376	599.75	248	599.45	25																	
377	629.92	378	624.90														36				
379	629.95	380	628.00														39				
380	628.00	311	627.48	42														1			
381	629.81	382	629.50														18				
383	630.23	384	629.50														52				
385	628.00	386	612.29														83				
387	588.47	324	586.50				380														
388	629.92	389	597.50														42		END SEWER @ TOP OF SLOPE		
390	602.39	143	601.89															1			
391	600.93	127	600.43															17			
392	598.60	100	598.10															1			
393	594.97	80	594.47															4			
394	593.50	74	593.00															4			
395	609.00	72	584.91																		
396	583.99	395	584.06											10		446					
397	613.00	398	600.00														148				
399	597.60	265	595.30				77										59				
409	###	413	###	x																	
410	###	411	###																		
411	###	412	###																		
412	###	413	###																		
413	599.71	414	597.84	14															END SEWER @ TOP OF SLOPE		
415	###	416	###																		
416	###	417	###																		
417	600.58	418	597.10	10															END SEWER @ TOP OF SLOPE		
418	587.89	414	587.32								301								373		
419	###	420	###																		
420	###	421	###																		
421	601.39	422	590.33	17															END SEWER @ TOP OF SLOPE		
422	588.33	104	588.07								138										
423	###	420	###																		

NOTE:
 SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT
 CONSTRUCTED IN GRADING & STRUCTURES CONTRACT.
 SHOWN FOR INFORMATION ONLY.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -6
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY JWM
 DATE 12/18/2006



12/18/2006
 \$FILES
 LAYOUT CLG 04/28/06
 DRAWN CLG 04/28/06
 REVIEWED JWB/JWM 04/28/06