

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	66
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

STORM SEWER SCHEDULE - 7

FROM #	INVERT ELEV	TO #	INVERT ELEV	STORM SEWER, CLASS A														TRENCHLESS PIPE INSTALLATION 72"	STORM SEWER JACKED IN PLACE SPECIAL	12" PIPE DRAINS SPECIAL	TRENCH BACKFILL	COMMENTS
				TYPE 1				TYPE 2				TYPE 3		TY 5	TYPE 6							
				12"	18"	24"	36"	42"	48"	54"	66"	54"	60"	72"	66"	18"	72"					
424	###	425	###																			
425	###	426	###																			
426	###	427	###																			
427	601.87	428	590.59	18																END SEWER @ TOP OF SLOPE		
428	588.59	422	588.33									137										
429	###	430	###																			
430	###	431	###																			
431	###	432	###																			
432	601.50	433	598.29	16																END SEWER @ TOP OF SLOPE		
433	588.85	428	588.59									135										
434	###	435	###																			
435	###	436	###																			
436	###	437	###																			
437	602.78	438	591.09	19																END SEWER @ TOP OF SLOPE		
438	589.09	433	588.85									122										
439	###	440	###																			
440	###	441	###																			
441	###	442	###																			
442	603.29	443	591.37	19																END SEWER @ TOP OF SLOPE		
443	589.37	438	589.09									142										
444	###	445	###																			
445	###	446	###																			
446	###	447	###																			
447	604.31	448	591.93	19																END SEWER @ TOP OF SLOPE		
448	589.93	132	589.60									166										
449	###	450	###																			
450	###	451	###																			
451	###	452	###																			
452	604.56	453	592.07	19																END SEWER @ TOP OF SLOPE		
453	590.07	448	589.93									68										
454	###	455	###																			
455	###	456	###																			
456	###	457	###																			
457	604.98	458	592.30	20																END SEWER @ TOP OF SLOPE		
458	590.30	453	590.07									117										
469	627.07	470	615.50														22			END SEWER @ TOP OF SLOPE		
471	627.31	472	615.50														40			END SEWER @ TOP OF SLOPE		
473	617.32	474	598.33														77			END SEWER @ TOP OF SLOPE		
475	617.38	476	598.33														74			END SEWER @ TOP OF SLOPE		
477	607.45	478	598.25														47			END SEWER @ TOP OF SLOPE		
479	608.08	480	598.25														45			END SEWER @ TOP OF SLOPE		
468	591.42	153	591.20									112										
482	605.17	483	602.67				30												1			
483	602.67	484	602.37				48												17			
484	602.37	485	602.17				12												8			
485	602.17	486	601.87				36												23			

NOTE:
 SHADED ITEMS INDICATE DRAINAGE STRUCTURES NOT CONSTRUCTED IN GRADING & STRUCTURES CONTRACT. SHOWN FOR INFORMATION ONLY.

REVISIONS		NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 STORM SEWER SCHEDULE -7
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)A,HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY JWM
 DATE 12/18/2006



© Copyright Hanson Professional Services Inc. 2006
 12/18/2006 \$FILES
 LAYOUT CLG 04/28/06
 DRAWN CLG 04/28/06
 REVIEWED JWB/JWM 04/28/06