

FAU ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8071	*	SANGAMON	559	68
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
(84-9-4)A,HBK,BY,BY-1 * 02-00382-02-PV				

PIPE CULVERT SCHEDULE

ROADWAY	STATION	UPSTREAM INVERT ELEV (FT)	DOWNSTREAM INVERT ELEV (FT)	TYPE 1 RCCP 18" ELLIPTICAL	TYPE 1 RCCP 24"	TYPE 1 RCCP 36"	TYPE 1 RCCP 48"	TYPE 6 RCCP 36"	RCCP 60" (SPECIAL)	TYPE 6 RCCP 72"	TYPE 2 RCCP 72"	PRECAST REINFORCED CONCRETE FLARED END SECTION ELLIPTICAL 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	PRECAST REINFORCED CONCRETE FLARED END SECTION 48"	PRECAST REINFORCED CONCRETE FLARED END SECTION 60"	PRECAST REINFORCED CONCRETE FLARED END SECTION 72"	MEDIAN INLET STD 604101	GRATING FOR CONCRETE FLARED END SECTION 36"	HEAVY DUTY EXCELSIOR BLANKET	TRENCH BACKFILL	
MACARTHUR	786+20.00	597.00	596.00					252						2						62	48	
MACARTHUR	790+20.00	592.00	591.00						309							2					70	63
MACARTHUR	794+20.00	598.50	598.00			302								2							62	45
MACARTHUR	800+30.00	599.64	599.57			166								2							62	
MACARTHUR	801+14.00	600.18	599.80			164								2							62	
MACARTHUR	815+00.00	598.50	598.50			202								2							62	38
RAMP A	21+40.00	594.00	593.60				116									2					64	57
RAMP B	25+00.00	589.00	587.00							191							2				76	6
RAMP D	52+00.00	597.20	597.00			120								4					2		124	24
REC DR	104+20.00	595.20	595.00			116								4					4		124	22
REC DR	125+25.00	596.50	594.50			60								2					2		62	11
I-72 LT	531+00.00					40								2					2		62	
I-72 LT	592+00.00	596.60	596.56		12								1								24	
I-72 RT	592+00.00	596.11	596.00		12								1								24	
I-72	592+00.00	NOTE 1																	1		36	
LINCOLNSHIRE	180+83.00	600.52	600.14	170									2								40	
LINCOLNSHIRE	180+80.00	600.52	600.14	177									2								40	
BORROW AREA OUTLET		580.85	580.85							119								2			76	
ENTRANCE MAC RT	770+31.00	594.92	594.64		44								2								48	
ENTRANCE MAC LT	821+70.50	600.40	600.28	32									2								40	
ENTRANCE REC DR LT	115+00.00	597.33	597.23	46									2								40	
ENTRANCE REC DR RT	115+00.00	597.33	597.23	46									2								40	
ENTRANCE REC DR LT	126+15.40	596.85	596.62	50									2								40	
BIKE PATH	12+13.00	599.65	599.60			26								2					2		62	6
BIKE PATH	34+00.00	600.00	598.36		47								2								48	3
BIKE PATH	42+60.00	598.50	598.50			21								2					2		62	7
BIKE PATH	49+06.00	600.40	600.28	32									2								40	
BIKE PATH	83+05.00	600.20	600.00			55								2							48	3
PARKING LOT ENT.	SOUTH	599.70	599.65	19									2								40	
PARKING LOT ENT.	NORTH	602.10	601.90	28									2								40	
-TOTALS-				600	115	1272	116	252	309	191	119	18	6	28	2	2	4	1	16	1680	332	

NOTE 1 -SET ON EXISTING PIPE

© Copyright Hanson Professional Services Inc. 2006



12/18/2006 \$FILES

LAYOUT	CLG	04/28/06
DRAWN	CLG	04/28/06
REVIEWED	JWB/JMW	04/28/06

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PIPE CULVERT SCHEDULE
 FAI-72, MACARTHUR BLVD
 SEC NO. 02-00382-02-PV
 SEC NO. (84-9-4)HBK,BY,BY-1
 SANGAMON COUNTY, ILLINOIS

SCALE: VERT. DRAWN BY CLG
 HORIZ. CHECKED BY JWB
 DATE 12/18/2006