

F.A.3. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	139B-1	SANGAMON	39	3A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES (CONTINUED)

LOCATION OF WORK
FAP 753 (IL RTE. 104)
APPROXIMATELY 4.33 MILES WEST OF AUBURN
SANGAMON COUNTY

80% FED./20% STATE
TOTAL QUANTITY
STP TWO-LANE
RURAL ROADWAY
X028-2A

PAYCODE	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	967
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	179
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	146
44000100	PAVEMENT REMOVAL	SQ YD	564
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	221
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	949
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	937
44200094	PAVEMENT PATCH, TYPE II, B"	SQ YD	12
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	60
48203100	HOT-MIX ASPHALT SHOULDERS	TON	148
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	73
50800105	REINFORCEMENT BARS	POUND	5990
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1710
51205200	TEMPORARY SHEET PILING	SQ FT	1114
51500100	NAME PLATES	EACH	1
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND SIZE 24"	EACH	2
54003000	CONCRETE BOX CULVERTS	CU YD	105.4
542A5479	PIPE CULVERTS CLASS A, TYPE 1, EQUIVALENT ROUND SIZE 24"	FOOT	60
54200229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	37
54213459	END SECTIONS 24"	EACH	2
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4
* 63200310	GUARD RAIL REMOVAL	FOOT	379
63300115	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, SINGLE RAIL	FOOT	177

*SPECIALTY ITEMS

Rev. 2-26-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 753 (IL RTE. 104)
SECTION 139B-1
SANGAMON COUNTY

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY