

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	139B-1	SANGAMON	39	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

LOCATION OF WORK
 FAP 753 (IL RTE. 104)
 APPROXIMATELY 4.33 MILES WEST OF AUBURN
 SANGAMON COUNTY

80% FED./20% STATE

TOTAL QUANTITY
 STP TWO-LANE
 RURAL ROADWAY

X028-2A

PAYCODE	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	28
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	94
20200100	EARTH EXCAVATION	CU YD	2390
20300100	CHANNEL EXCAVATION	CU YD	540
25000200	SEEDING, CLASS 2	ACRE	2.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	207
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	207
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	207
25100115	MULCH, METHOD 2	ACRE	2.3
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	230
28000300	TEMPORARY DITCH CHECKS	EACH	25
28000900	FENCE (EROSION CONTROL)	FOOT	80
28100107	STONE RIPRAP, CLASS A4	SQ YD	582
28200200	FILTER FABRIC	SQ YD	582
35101400	AGGREGATE BASE COURSE, TYPE B	TON	277
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	1426
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.0
40600300	AGGREGATE (PRIME COAT)	TON	8.0
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	333
40600990	TEMPORARY RAMP	SQ YD	26

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 753 (IL RTE. 104)
 SECTION 139B-1
 SANGAMON COUNTY

SCALE: VERT.
 DATE: HORIZ.

DRAWN BY
 CHECKED BY