

CONTRACT NO. 72449

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	405RS-4	MONTGOMERY	75	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS & SYMBOLS

LOCATION	QUANTITY (SQ FT)
F. A. P. 777 (IL 185)	
STA. 392+07.00 RT	
"R"	7.20
"X"	54
STA. 398+76.00 LT	
"R"	7.20
"X"	54
PROJECT TOTAL	123

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	QUANTITY (EACH)
F. A. P. 777 (IL 185)	
STA. 1079+70.07 to STA 1079+89.56	1
STA EQUATION #1 STA. 1079+89.56 (BK) to 79+92.12 (AH)	
STA. 79+92.12 to STA 310+06.50	288
BRIDGE OMISSION (S. N. 068-0026) STA. 310+06.50 to 310+49.12	
STA. 310+49.12 to STA. 359+46.68	62
STA. 359+46.68 to STA. 395+01.30	89
RAILROAD OMISSION STA. 395+01.30 to 395+10.40	
STA EQUATION #2 STA. 395+31.53 (BK) to 395+51.00 (AH)	
RAILROAD OMISSION STA. 395+73.70 to 395+82.70	
STA. 395+82.70 to STA. 399+66.50	5
PROJECT TOTAL	445

SCHEDULE OF QUANTITIES

RAISED REFLECTIVE PAVEMENT MARKING REMOVAL

LOCATION	QUANTITY (EACH)
F. A. P. 777 (IL 185)	
(Beginning of Project to Buckeye Tr.)	26
(Buckeye Tr. to 9th St.)	27
(9th St. to School House Rd.)	123
(School House Rd. to 14th Rd.)	21
(14th Rd. to S. N. 068-0026)	91
(S. N. 068-0026 to McDavid Cem. Ln.)	12
(McDavid Cem. Ln. to CIPS Tr.)	28
(CIPS Tr. to Coffeen Rd.)	23
(Coffeen Rd. to James St.)	4
(James St. to Western St.)	8
(Western St. to N. Central St.)	5
(N. Central St. to Short St.)	5
(Short St. to Park St.)	3
(Park St. to Prospect)	5
(Prospect to N. Church St.)	4
(N. Church St. to Stoddard Rd.)	5
(Stoddard Rd. to Locust)	1
(Locust to Elm St.)	1
(Elm St. to R. R.)	2
(R. R. to End of Project)	5
PROJECT SUB-TOTAL	399

STEEL PLATE BEAM GUARDRAIL, TYPE A

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185)	
△ STA. 308+24.00 to 309+86.50 RT	162.5
STA. 307+74.00 to 309+86.50 LT	212.5
BRIDGE OMISSION (S. N. 068-0026) STA. 310+06.50 to 310+49.12	
STA. 310+69.12 to 312+19.12 RT	162.5
STA. 310+69.12 to 312+44.12 LT	175
△ STA. 352+25.68 to 354+13.18 RT	187.5
PROJECT TOTAL	712.5

TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

LOCATION	QUANTITY (EACH)
F. A. U. 777 (IL 185)	
△ STA. 307+74.00 to 308+24.00 RT	1
STA. 307+24.00 to 307+74.00 LT	1
BRIDGE OMISSION S. N. : 068-0026 STA. 310+06.50 to STA 310+49.12	
STA. 312+19.12 to 312+69.12 RT	1
STA. 312+44.12 to 312+94.12 LT	1
PROJECT TOTAL	4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. Route 777 (IL 185)
 Section 405RS-4
 MONTGOMERY COUNTY

SCALE: VERT. HORIZ.
 DATE DECEMBER 23, 2005
 DRAWN BY JWC
 CHECKED BY RSC

△ Rev. 2-20-07

PLOT DATE = 12/21/2006
 FILE NAME = G:\projects\405RS-4\405RS-4.dgn
 USER NAME = cskj