

CONTRACT NO. 72449

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	405RS-4	MONTGOMERY	75	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

PAINT PAVEMENT MARKING - LINE

LOCATION	5"		6"	
	YELLOW		WHITE	WHITE
	SOLID (FOOT)	SKIP - DASH (FOOT)	SOLID (FOOT)	SOLID (FOOT)
F. A. P. 777 (IL 185)				
STA. 1079+70.07 to 1079+89.56		4.87	38.98	
<i>STA EQUATION #1</i>				
<i>STA. 1079+89.56 (BK) to 79+92.12 (AH)</i>				
STA. 79+92.12 to 362+30.00		7,059.47	56,475.76	
STA. 124+07.80 to 125+07.80 RT				100
STA. 287+20.00 to 328+50.00	4,130			
(Subtract Side Roads)			-320	
PROJECT SUB-TOTAL	4,130	7,064.34	56,194.74	100
PROJECT TOTAL		67,389		100

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	YELLOW	YELLOW	YELLOW	WHITE
	SOLID	SKIP DASH	DOUBLE SOLID	SOLID
	(FOOT)	(FOOT)	(FOOT)	(FOOT)
F. A. U. 777 (IL 185)				
STA. 362+30.00 to 394+74.76		811.19		
STA. 362+30.00 to 395+01.30				6,542.54
STA. 388+50.00 to 394+74.76	624.76			
STA. 394+74.76 to 395+01.30			53.08	
<i>RAILROAD OMISSION</i>				
<i>STA. 395+01.30 to 395+10.40</i>				
STA. 395+10.40 to 395+31.53			42.26	42.26
<i>STA EQUATION #2</i>				
<i>STA. 395+31.53 (BK) to 395+51.00 (AH)</i>				
STA. 395+51.00 to 395+73.70			45.40	45.40
<i>RAILROAD OMISSION</i>				
<i>STA. 395+73.70 to 395+82.70</i>				
STA. 395+82.70 to 397+17.00			537.20	
STA. 395+82.70 to 399+66.50				767.60
STA. 397+17.00 to 399+66.50	249.50	62.38		
(Subtract Side Roads)				-480
PROJECT SUB-TOTAL	874.26	873.57	677.94	6,917.80
PROJECT TOTAL			9,344	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"

LOCATION	QUANTITY (FOOT)
F. A. P. 777 (IL 185)	
STA. 391+83.00 RT	11
STA. 392+33.00 RT	11
STA. 394+41.00 RT	11
<i>RAILROAD OMISSION</i>	
<i>STA. 395+01.27 to 395+10.40</i>	
<i>STA EQUATION #2</i>	
<i>STA. 395+31.53 (BK) to 395+51.00 (AH)</i>	
<i>RAILROAD OMISSION</i>	
<i>STA. 395+73.70 to 395+82.70</i>	
STA. 396+11.00 LT	12
STA. 398+50.00 LT	12
STA. 399+00.00 LT	12
PROJECT TOTAL	69

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.P. Route 777 (IL 185)
 Section 405RS-4
 MONTGOMERY COUNTY

SCALE: VERT. DRAWN BY JWC
 HORIZ. CHECKED BY RSC
 DATE DECEMBER 23, 2005

PLOT DATE = 12/8/2005
 FILE NAME = c:\projects\4656802\shschedule.dgn
 PLOT SCALE = 50.0000' / 1"
 USER NAME = cckjw