

CONTRACT NO. 72449

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|---------|---------------------------|--------------|-----------|
| 777 | 405RS-4 | MONTGOMERY | 75 | 13 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

PREFORMED PLASTIC PAVEMENT
MARKING, TYPE B - LETTERS & SYMBOLS

| LOCATION | QUANTITY (SQ FT) |
|-----------------------|------------------|
| F. A. P. 777 (IL 185) | |
| STA. 392+07.00 RT | |
| "R" | 7.20 |
| "X" | 54 |
| STA. 398+76.00 LT | |
| "R" | 7.20 |
| "X" | 54 |
| PROJECT TOTAL | 123 |

RAISED REFLECTIVE
PAVEMENT MARKER

| LOCATION | QUANTITY (EACH) |
|---|-----------------|
| F. A. P. 777 (IL 185) | |
| STA. 1079+70.07 to STA 1079+89.56 | 1 |
| STA EQUATION #1 STA. 1079+89.56 (BK) to 79+92.12 (AH) | |
| STA. 79+92.12 to STA 310+06.50 | 288 |
| BRIDGE OMISSION (S. N. 068-0026) STA. 310+06.50 to 310+49.12 | |
| STA. 310+49.12 to STA. 359+46.68 | 62 |
| STA. 359+46.68 to STA. 395+01.30 | 89 |
| RAILROAD OMISSION STA. 395+01.30 to 395+10.40 | |
| STA EQUATION #2 STA. 395+31.53 (BK) to 395+51.00 (AH) | |
| RAILROAD OMISSION STA. 395+73.70 to 395+82.70 | |
| STA. 395+82.70 to STA. 399+66.50 | 5 |
| PROJECT TOTAL | 445 |

SCHEDULE OF QUANTITIES

RAISED REFLECTIVE PAVEMENT
MARKING REMOVAL

| LOCATION | QUANTITY (EACH) |
|---------------------------------------|-----------------|
| F. A. P. 777 (IL 185) | |
| (Beginning of Project to Buckeye Tr.) | 26 |
| (Buckeye Tr. to 9th St.) | 27 |
| (9th St. to School House Rd.) | 123 |
| (School House Rd. to 14th Rd.) | 21 |
| (14th Rd. to S. N. 068-0026) | 91 |
| (S. N. 068-0026 to McDavid Cem. Ln.) | 12 |
| (McDavid Cem. Ln. to CIPS Tr.) | 28 |
| (CIPS Tr. to Coffeen Rd.) | 23 |
| (Coffeen Rd. to James St.) | 4 |
| (James St. to Western St.) | 8 |
| (Western St. to N. Central St.) | 5 |
| (N. Central St. to Short St.) | 5 |
| (Short St. to Park St.) | 3 |
| (Park St. to Prospect) | 5 |
| (Prospect to N. Church St.) | 4 |
| (N. Church St. to Stoddard Rd.) | 5 |
| (Stoddard Rd. to Locust) | 1 |
| (Locust to Elm St.) | 1 |
| (Elm St. to R. R.) | 2 |
| (R. R. to End of Project) | 5 |
| PROJECT SUB-TOTAL | 399 |

STEEL PLATE BEAM
GUARDRAIL, TYPE A

| LOCATION | QUANTITY (FOOT) |
|---|-----------------|
| F. A. P. 777 (IL 185) | |
| STA. 306+74.00 to 309+86.50 RT | 312.5 |
| STA. 307+74.00 to 309+86.50 LT | 212.5 |
| BRIDGE OMISSION (S. N. 068-0026) STA. 310+06.50 to 310+49.12 | |
| STA. 310+69.12 to 312+19.12 RT | 162.5 |
| STA. 310+69.12 to 312+44.12 LT | 175 |
| STA. 352+25.68 to 354+13.18 RT | 187.5 |
| PROJECT TOTAL | 1,050 |

TRAFFIC BARRIER TERMINAL,
TYPE 1, SPECIAL (TANGENT)

| LOCATION | QUANTITY (EACH) |
|---|-----------------|
| F. A. U. 777 (IL 185) | |
| STA. 306+24.00 to 306+74.00 RT | 1 |
| STA. 307+24.00 to 307+74.00 LT | 1 |
| BRIDGE OMISSION S. N. : 068-0026 STA. 310+06.50 to STA 310+49.12 | |
| STA. 312+19.12 to 312+69.12 RT | 1 |
| STA. 312+44.12 to 312+94.12 LT | 1 |
| PROJECT TOTAL | 4 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
F.A.P. Route 777 (IL 185)
Section 405RS-4
MONTGOMERY COUNTY

SCALE: VERT. HORIZ.
DATE DECEMBER 23, 2005
DRAWN BY JWC
CHECKED BY RSC

PLOT DATE = 12/29/2005
FILE NAME = c:\projects\4656802\shitschedules.dgn
PLOT SCALE = 50.0000 / 1 IN.
USER NAME = ccoyle