

CONTRACT NO. 72449

F.A.P. RTE. 777	SECTION 405RS-4	COUNTY MONTGOMERY	TOTAL SHEETS 75	SHEET NO. 14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STEEL PLATE BEAM
GUARDRAIL REMOVAL

LOCATION	QUANTITY (FOOT)
F. A. U. 777 (IL 185)	
STA. 143+12.50 to 143+37.50 RT	25
STA. 143+37.50 to 145+75.00 RT	237.5
STA. 144+93.50 to 145+18.50 LT	25
STA. 145+18.50 to 146+31.00 LT	112.5
STA. 145+75.00 to 146+00.00 RT	25
STA. 146+31.00 to 146+56.00 LT	25
STA. 190+50.00 to 191+00.00 RT	50
STA. 191+00.00 to 192+50.00 RT	150
STA. 191+35.00 to 191+60.00 LT	25
STA. 191+60.00 to 193+10.00 LT	150
STA. 192+50.00 to 192+75.00 RT	25
STA. 193+10.00 to 193+35.00 LT	25
STA. 267+26.00 to 267+51.00 RT	25
STA. 267+51.00 to 268+88.50 RT	137.5
STA. 267+93.50 to 268+18.50 LT	25
STA. 268+18.50 to 269+56.00 LT	137.5
STA. 268+88.50 to 269+13.50 RT	25
STA. 269+56.00 to 269+81.00 LT	25
STA. 307+24.00 to 307+49.00 LT	25
STA. 307+49.00 to 309+86.50 LT	237.5
STA. 308+36.50 to 308+61.50 RT	25
STA. 308+61.50 to 309+86.50 LT	125
BRIDGE OMISSION S. N. : 068-0026	
STA. 310+06.50 to STA 310+49.12	
STA. 310+69.12 to 312+44.12 RT	175
STA. 310+69.12 to 312+69.12 LT	200
STA. 312+44.12 to 312+69.12 RT	25
STA. 312+69.12 to 312+94.12 LT	25
STA. 351+75.68 to 352+00.68 RT	25
STA. 352+00.68 to 354+38.18 RT	237.5
STA. 352+63.18 to 352+88.18 LT	25
STA. 352+88.18 to 355+25.68 LT	237.5
STA. 354+38.18 to 354+63.18 RT	25
STA. 355+25.68 to 355+50.68 LT	25
PROJECT TOTAL	2,662.5

SCHEDULE OF QUANTITIES

GUARDRAIL MARKERS, TYPE B

LOCATION	QUANTITY (EACH)
F. A. U. 777 (IL 185)	
STA. 306+24.00 to 306+74.00 RT	1
STA. 306+74.00 to 309+86.50 RT	3
STA. 307+24.00 to 307+74.00 LT	2
STA. 307+74.00 to 309+86.50 LT	1
BRIDGE OMISSION (S. N. 068-0026)	
STA. 310+06.50 to 310+49.12	
STA. 310+69.12 to 312+19.12 RT	2
STA. 312+19.12 to 312+69.12 RT	1
STA. 312+69.12 to 312+44.12 LT	2
STA. 312+44.12 to 312+94.12 LT	1
PROJECT TOTAL	13

GRATES, SPECIAL

LOCATION	QUANTITY (EACH)
F. A. P. 777 (IL 185)	
STA. 145+08.90 (RT & LT)	2
STA. 192+00.00 (RT & LT)	2
STA. 268+53.50 (RT & LT)	2
STA. 353+66.50 (LT)	2
PROJECT TOTAL	8

EARTH EXCAVATION (SPECIAL)

LOCATION	QUANTITY (CU YD)
F. A. P. 777 (IL 185)	
PARKING LANES:	
100% CITY OF COFFEEN	
STA. 391+12.00 to 393+52.40 RT	6
PROJECT TOTAL	6

TERMINAL MARKER - DIRECT APPLIED

LOCATION	QUANTITY (EACH)
F. A. U. 777 (IL 185)	
STA. 306+24.00 RT	1
STA. 307+24.00 LT	1
BRIDGE OMISSION (S. N. 068-0026)	
STA. 310+06.50 to 310+49.12	
STA. 312+69.12 RT	1
STA. 312+94.12 LT	1
PROJECT TOTAL	4

EARTH EXCAVATION (WIDENING)

LOCATION	QUANTITY (CU YD)
F. A. P. 777 (IL 185)	
STA. 359+46.68 to 386+43.80 RT	83.24
STA. 359+46.68 to 386+49.30 LT	92.67
PROJECT TOTAL	176

PLOT DATE = 12/8/2006
FILE NAME = c:\projects\6656802\shitschedules.dgn
PLOT SCALE = 56.0000 / IN
USER NAME = coxjr

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
F.A.P. Route 777 (IL 185)
Section 405RS-4
MONTGOMERY COUNTY
SCALE: VERT. DRAWN BY JWC
 HORIZ. CHECKED BY RSC
DATE DECEMBER 23, 2005