

CONTRACT NO. 72449

F.A.P. RTE. 777	SECTION 405RS-4	COUNTY MONTGOMERY	TOTAL SHEETS 75	SHEET NO. 18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

PAVEMENT SCHEDULE												
LOCATION STATION TO STATION	LT OR RT	LENGTH (FT)	EXIST PAVE WIDTH (FT)	HMA BINDER THICKNESS (IN)	HMA SURF THICKNESS (IN)	HMA SURF REMOVAL BUTT - JOINT (SQ YD)	HMA SURF REMOVAL (VAR. DEPTH) (SQ YD)	HMA SURF REMOVAL (2") (SQ YD)	HMA CONC BINDER CSE IL-19.0, N50 (TON)	HMA CONC SURF CSE "C" N50 (TON)	BIT MAT PRIME CT (TON)	AGG PRIME CT (TON)
FAP 777 (IL 185)												
Parking Lanes:												
STA. 388+32.00 TO STA. 391+12.00	RT	280.00	9	-	-	-	280.00	-	-	-	0.11	0.56
STA. 388+78.80 TO STA. 390+80.65	LT	201.85	11	-	-	-	246.71	-	-	-	0.09	0.49
STA. 391+12.00 TO STA. 393+52.40	RT	240.40	11	-	-	-	293.82	-	-	-	0.11	0.59
(Measured Using CADD) Area=787.51												
STA. 391+12.00 TO STA. 393+52.40	RT	787.51	-	-	-	-	87.50	-	-	-	0.03	0.18
(Measured Using CADD) Area=921.12												
STA. 391+27.00 TO STA. 393+58.00	LT	921.12	-	-	-	-	102.35	-	-	-	0.04	0.20
STA. 391+32.30 TO STA. 393+58.00	LT	225.70	11	-	-	-	269.13	-	-	-	0.10	0.54
(Measured Using CADD) Area=69.44												
STA. 393+58.00 TO STA. 394+45.00	RT	69.44	-	-	-	-	69.44	-	-	-	0.03	0.14
STA. 393+58.00 TO STA. 394+57.00	LT	99.00	10	-	-	-	110.00	-	-	-	0.04	0.22
(Measured Using CADD) Area=10.72												
STA. 394+93.30 TO R.R.	LT	10.72	-	-	-	-	10.72	-	-	-	0.00	0.02
6' Bituminous Shoulder												
STA. 393+92.00 TO STA. 394+45.00	RT	53.00	6	-	-	-	33.33	-	-	-	0.01	0.07
STA. 394+91.30 TO STA. 395+01.30		10.00	32	-	-	35.56	-	-	-	-	0.01	0.07
RAILROAD OMISSION STA. 395+01.30 to 395+10.40												
STA. 395+10.40 TO STA. 395+20.40		10.00	24	-	-	26.67	-	-	-	-	0.01	0.05
STA. 395+10.40 TO STA. 395+31.53		21.13	24	-	-	-	-	-	-	6.31	-	-
STA. 395+20.40 TO STA. 395+31.53		11.13	24	-	-	-	-	29.68	-	-	0.01	0.06
(STA. EQ. #2) 395+31.53 BK. = 395+51.00 AH.												
STA. 395+51.00 TO STA. 395+63.70		12.70	24	-	-	-	-	33.87	-	-	0.01	0.07
STA. 395+63.70 TO STA. 395+73.70		10.00	24	-	-	26.67	-	-	-	-	0.01	0.05
STA. 395+51.00 TO STA. 395+73.70		22.70	24	-	-	-	-	-	-	6.78	-	-
RAILROAD OMISSION STA. 395+73.70 to 395+82.70												
STA. 395+82.70 TO STA. 395+92.70		10.00	26	-	-	28.89	-	-	-	-	0.01	0.06
STA. 395+92.70 TO STA. 399+56.50		363.80	26	-	-	-	-	1,050.98	-	-	0.40	2.10
STA. 399+56.50 TO STA. 399+66.50		10.00	26	-	-	28.89	-	-	-	-	0.01	0.06
STA. 395+82.70 TO STA. 399+66.50		383.80	26	-	-	-	-	-	-	124.18	-	-
Incidental Bituminous Surfacing (Bit P.E.'s & Side Roads)												
		-	-	-	-	-	2,361.83	-	-	-	0.90	4.72
Incidental Bituminous Surfacing (Agg P.E.'s & C.E.'s)												
		-	-	-	-	-	-	-	-	-	0.23	-
Earth Excavation (Special) 53 SY												
		53.00	-	-	-	-	-	-	-	-	0.02	-
Total for Bit Surf Rem VD for Parking Lanes												
50% / 50% (State and City of Coffeen) 1280 SY												
		-	-	-	-	-	-	-	-	-	0.49	2.56
100% (City of Coffeen) 190 SY												
		-	-	-	-	-	-	-	-	-	0.07	0.38
SUB-TOTAL PG 2												
						146.67	3,864.83	1,114.52	0.00	137.27	2.76	13.19
TOTAL												
						326	87,979	13,089	8,268	7,021	40	206

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. Route 777 (IL 185)
Section 405RS-4
MONTGOMERY COUNTY

SCALE: VERT. DRAWN BY JWC
HORIZ. CHECKED BY RSC
DATE DECEMBER 23, 2005

PLOT DATE = 12/8/2006
 FILE NAME = c:\projects\465682\shitschedule.dgn
 PLOT SCALE = 50.0000 / IN
 USER NAME = coxjm