

CONTRACT NO. 72693

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
777	405RS-4	MONTGOMERY	75	64
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

INCIDENTAL HOT-MIX ASPHALT SCHEDULE

DESCRIPTION	STATION	PROPOSED				AGGR. ENTR.		HMA. ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)
		WIDTH (FOOT)	LENGTH (FOOT)	THICKNESS		AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)	AREA (SQ FT)	TOTAL (TON)		
				VAR. FR. (FOOT)	AVG. (FOOT)								
(Locust) LT	391+11.00 LT	30	16	2 to 1.5	1.75					736.00	8.01	8.01	162.00
PCC CE (LT)	391+80.00 LT												
HMA CE (RT)	393+80.00 RT	33	9	2 to 1.5	1.75			378.00	4.12			4.12	124.50
AGG CE (LT)	394+03.00 LT	17	3		8	60.00	2.99					2.99	64.50
HMA CE (RT)	394+64.00 RT	36	9	2 to 1.5	1.75					405.00	4.41	4.41	129.00
(Elm St.) LT	394+76.00 LT	36	10	2 to 1.5	1.75					460.00	5.01	5.01	135.00
RAILROAD OMISSION:	395+01.30												
	395+10.40												
STA. EQUATION #1	395+31.53												
	395+51.00												
RAILROAD OMISSION:	395+73.70												
	395+82.70												
(Cundiff St.) RT	395+91.00 RT	66	9	2 to 1.5	1.75					675.00	7.35	7.35	174.00
HMA CE (RT)	397+14.00 RT	30	9	2 to 1.5	1.75			351.00	3.82			3.82	120.00
HMA PE (LT)	397+17.00 LT	28	7	2 to 1.5	1.75			245.00	2.67			2.67	105.00
HMA CE (RT)	397+90.00 RT	36	9	2 to 1.5	1.75			405.00	4.41			4.41	129.00
HMA CE (RT)	398+53.00 RT	37	9	2 to 1.5	1.75			414.00	4.51			4.51	130.50
(Chapman Tr.) LT	395+91.00 LT	55	9	2 to 1.5	1.75					576.00	6.27	6.27	157.50
SECTION BEGINS	399+56.50												
LIMITS OF IMPROVEMENT	399+66.50												
Subtotal (pg 2) =						60.00	2.99	1,793.00	19.52	2,852.00	31.06	53.57	1,431.00
Total =						5,545.00	129.24	9,990.50	134.60	11,266.00	138.42	402.27	8,394.00
100% Coffeen												3.99	
Total =												406.26	

* QUANTITIES HAVE INCLUDED MAILBOX TURNOUTS WHICH SHALL BE BROUGHT UP TO GRADE USING INCIDENTAL HOT-MIX ASPHALT SURFACING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
DETAILS FOR RURAL ENTRANCE, MAILBOX TURNOUT & SIDE ROAD
 SHEET 5 OF 5
 SCALE: VERT. / HORIZ.
 DATE: DECEMBER 2, 2005
 DRAWN BY: CAD
 CHECKED BY: JCN

PLOT DATE = 12/16/2006
 FILE NAME = c:\projects\ad656802\details.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = csn