CONTRACT NO. 72826

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D 6 RESURFACING 2007

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

			80% FED. 20% STATE	IL 29: CHENEY TO IL 48	IL 29: IL 48 TO KENNEDY, LAKE TO VELMA RD	IL 29: KENNEDY TO LAKE	SN 011-0010: IL 29 OVER IL 48	SN 011-0011: IL 29 OVER FLAT BRANCH	STORM SEWER IMPROVMENTS
	LOCATION OF WORK			URBAN	RURAL	RURAL	RURAL	RURAL	URBAN
	SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000	SFTY-2A	SFTY-2A	Y007
20200500	EARTH EXCAVATION (WIDENING)	CU YD	1715		1715				
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.21						0.21
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	44	24.7	12.3	6.4	0.3	0.3	
40600300	AGGREGATE (PRIME COAT)	TON	231	130	65	34	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1852		1332	520			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	2286		989	1,297			
40600990	TEMPORARY RAMP	SQ YD	1060	723	294	43			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,712	6914	2664	1,040	46.4	47.6	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	490	325	56	109			
44000152	HOT-MIX ASPHALT SURFACE REMOVAL 3/4"	SQ YD	1337				660	677	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	65,002	65,002					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	47,128		31,526	15,602			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	625	625					
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	1,395	815	580				
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	640	325	315				
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	675	360	315				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1588	173	731	684			
48203029	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	7699		7699				
48203100	HOT-MIX ASPHALT SHOULDERS	TON	376			376			
51205200	TEMPORARY SHEET PILING	SQ FT	4,000						4,000
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	221						221
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1						1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1						1
60255500	MANHOLES TO BE ADJUSTED	EACH	13	12		1			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	22	22					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	625	625					
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	6,100			1,388	4,712		
64200105	SHOULDER RUMBLE STRIPS	FOOT	29,812		15,371	14,441			

Rev.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAP 75 (IL 29)
SECTION D 6 RESURFACING 2007
CHRISTIAN COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

Rev. 2-22-07

Rev.

PLOT DATE : 12/20/2006
FILE NAME : c:\pwworking\ed\d0754683\squ.dgn
PLOT SCALE : 42.3529 ' / IN.
USER NAME : leughlsw