

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*D 6 RESURFACING 2007

LEVEL BINDER (MACHINE METHOD), N70

LOCATION	PAVEMENT WIDTH (FOOT)	PAVEMENT AREA (SQ YD)	TONS
I-29 MAINLINE			
STA 28+80.00 TO STA 41+98.04 BK	24	3,514.77	147.62
STA 42+39.60 AH TO STA 58+66.00 BK	24	4,337.07	182.16
STA 58+70.03 AH TO STA 58+79.00	24	23.92	1.00
STA 60+81.00 TO STA 100+89.78	24	10,690.08	448.98
STA 100+89.78 TO STA 102+35.45	24	388.45	16.31
STA 102+35.45 TO STA 107+29.75	26 TO 36	1,702.59	71.51
STA 107+29.75 TO STA 110+72.28	36	1,370.12	57.55
STA 110+72.28 TO STA 113+67.47	36 TO 26	1,016.77	42.70
STA 113+67.47 TO STA 119+82.61	24	1,640.37	68.90
STA 119+82.61 TO STA 124+54.86	26 TO 36	1,626.64	68.32
STA 124+54.86 TO STA 129+69.26	36	2,057.60	86.42
STA 129+69.26 TO STA 137+17.09	36 TO 26	2,575.86	106.19
STA 137+17.09 TO STA 154+00.00	24	4,487.76	188.49
STA 174+00.00 TO STA 206+47.00	24	8,658.67	363.66
TOTAL			1,851.81

HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)

LOCATION	PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)
I-29 MAINLINE				
STA 29+15.00 TO STA 41+98.04 BK	24			3,421.44
STA 42+39.60 AH TO STA 58+66.00 BK	24			4,337.07
STA 58+70.03 AH TO STA 58+79.00	24			23.92
STA 58+79.00 TO STA 60+81.00	BRIDGE OMISSION			
STA 60+81.00 TO STA 100+89.78	24			10,690.08
STA 100+89.78 TO STA 102+35.45	24	4	4	517.94
STA 102+35.45 TO STA 107+29.75	26 TO 36	4	4	2,141.97
STA 107+29.75 TO STA 110+72.28	36	4	4	1,674.59
STA 110+72.28 TO STA 113+67.47	36 TO 26	4	4	1,279.16
STA 113+67.47 TO STA 119+82.61	24	4	4	2,187.16
STA 119+82.61 TO STA 124+54.86	26 TO 36	4	4	2,046.42
STA 124+54.86 TO STA 129+69.26	36	4	4	2,514.84
STA 129+69.26 TO STA 137+17.09	36 TO 26	4	4	3,240.60
STA 137+17.09 TO STA 154+00.00	24			4,487.76
STA 174+00.00 TO STA 206+12.00	24			8,565.33
TOTAL				47,128.28

HOT-MIX ASPHALT SURFACE REMOVAL 2"

LOCATION	LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)
I-29 MAINLINE			
STA 520+72.00 TO STA 524+01.34	329.34	52	1,902.85
STA 524+01.34 TO STA 526+85.47	284.13	VAR	2,692.71 *
STA 526+85.47 TO STA 552+05.00	2,519.53	40	11,197.91
STA 552+05.00 TO STA 554+07.00	202.00	40 TO 48	987.56
STA 554+07.00 TO STA 564+80.00	1,073.00	48	5,722.67
STA 564+80.00 TO STA 570+17.12	537.12	48 TO 50	2,924.32
STA 570+17.12 TO STA 572+17.12	200.00	50 TO 60	1,222.22
STA 572+17.12 TO STA 577+05.51	488.39	60 TO 62	3,310.20
STA 577+05.51 TO STA 583+11.84	606.33	VAR	5,596.03 **
STA 583+11.84 TO STA 583+24.00	12.16	48	64.85
STA 47+07.92 TO STA 49+22.00	214.08	48 TO 33	963.36
STA 49+22.00 TO STA 54+22.00	500.00	33	1,833.33
STA 54+22.00 TO STA 55+37.00	115.00	33 TO 30	402.50
STA 55+37.00 TO STA 56+92.00	155.00	30 TO 21	439.17
STA 56+92.00 TO STA 59+46.00	254.00	24	677.33
STA 59+46.00 TO STA 60+66.00	120.00	24 TO 33	380.00
STA 60+66.00 TO STA 63+74.00	308.00	33	1,129.33
STA 63+74.00 TO STA 64+66.00	92.00	33 TO 30	322.00
STA 64+66.00 TO STA 65+99.00	133.00	30 TO 24	399.00
STA 65+99.00 TO STA 79+89.00	1,390.00	24	3,706.67
STA 79+89.00 TO STA 84+78.00	489.00	27	1,467.00
STA 84+78.00 TO STA 87+81.23	303.23	VAR	1,026.15
STA 7+18.82 TO STA 13+43.26	624.44	VAR	2,394.36
STA 13+43.26 TO STA 15+31.02	187.76	VAR	1,592.09 ***
STA 15+31.02 TO STA 17+42.49	211.47	42	859.79
STA 17+42.49 TO STA 26+00.00	857.51	VAR	5,473.81 ****
STA 26+00.00 TO STA 27+47.00	147.00	30 TO 28	473.67
SIDE STREETS/ROADS & ENTRANCES (SEE SCHEDULE ON SHEET 97)			3,268.57
PG TOTAL			59,160.88
JOB TOTAL			62,429.45

EARTH EXCAVATION WIDENING

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	DEPTH (INCH)	VOLUME (CU YD)
I-29 MAINLINE				
STA 28+80.00 TO STA 31+19.00	3	3	8	35.41
STA 32+05.00 TO STA 39+52.00	0	3	8	55.33
STA 32+05.00 TO STA 39+86.00	3	0	8	57.85
STA 40+28.00 TO STA 41+98.04 BK	0	3	8	12.60
STA 40+50.00 TO STA 41+98.04 BK	3	0	8	10.97
STA 42+39.60 AH TO STA 58+66.00 BK	3	3	8	240.95
STA 58+70.03 AH TO STA 58+79.00	3	3	8	1.33
STA 60+81.00 TO STA 79+60.00	0	3	8	139.19
STA 60+81.00 TO STA 80+05.00	3	0	8	142.52
STA 80+48.00 TO STA 100+89.78	0	3	8	151.24
STA 80+45.00 TO STA 100+89.78	3	0	8	151.47
STA 137+17.09 TO STA 154+00.00	0	3	8	124.66
STA 174+00.00 TO STA 204+26.00	0	3	8	224.15
STA 137+17.09 TO STA 139+21.00	3	0	8	15.10
STA 139+75.00 TO STA 154+00.00	3	0	8	105.56
STA 174+00.00 TO STA 204+16.00	3	0	8	223.41
STA 205+27.00 TO STA 206+47.00	0	3	8	8.89
STA 205+09.00 TO STA 206+47.00	3	0	8	10.22
TOTAL				1,710.85

- * CHEYNEY INTERSECTION
- ** McADAM INTERSECTION
- *** WEBSTER/PARK INTERSECTION
- **** MAIN CROSS/LINCOLN TRAIL. INT.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

FAP 75 (IL 29)
SECTION D 6 RESURFACING 2007
CHRISTIAN COUNTY

SCALE: VERT. DATE HORIZ. DATE DRAWN BY CHECKED BY

Rev. Sheet 2-22-07