CONTRACT NO. 72826

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	31
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*D 6 RESURFACING 2007

AGGREGATE (PRIME COAT)

LOCATION			PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)	QUANTITY (TONS)	
I-29 MAINLINE								
STA 520+72.00	TO	STA 524+01.34	52			1,902.85	3.81	
STA 524+01.34	TO	STA 526+85.47	VAR			2,692.71	5.39	*
STA 526+85.47	TO	STA 552+05.00	40			11,197.91	22.40	
STA 552+05.00	TO	STA 554+07.00	40 TO 48			987.56	1.98	
STA 554+07.00	TO	STA 564+80.00	48			5,722.67	11.45	
STA 564+80.00	TO	STA 570+17.12	48 TO 50			2,924.32	5.85	
STA 570+17.12	TO	STA 572+17.12	50 TO 60			1,222.22	2.44	
STA 572+17.12	TO	STA 577+05.51	60 TO 62			3,310.20	6.62	
STA 577+05.51	TO	STA 583+11.84	VAR			5,596.03	11.19	**
STA 583+11.84	TO	STA 583+24.00	48			64.85	0.13	
STA 47+07.92	TO	STA 49+22.00	48 TO 33			963.36	1.93	
STA 49+22.00	TO	STA 54+22.00	33			1,833.33	3.67	
STA 54+22.00	TO	STA 55+37.00	33 TO 30			402.50	0.81	
STA 55+37.00	TO	STA 56+92.00	30 TO 21			439.17	0.88	
STA 56+92.00	TO	STA 59+46.00	24			677.33	1.35	
STA 59+46.00	TO	STA 60+66.00	24 TO 33			380.00	0.76	
STA 60+66.00	TO	STA 63+74.00	33			1,129.33	2.26	
STA 63+74.00	TO	STA 64+66.00	33 TO 30			322.00	0.64	
STA 64+66.00	TO	STA 65+99.00	30 TO 24			399.00	0.80	
STA 65+99.00	TO	STA 79+89.00	24			3,706.67	7.41	
STA 79+89.00	TO	STA 84+78.00	27			1,467.00	2.93	
STA 84+78.00	TO	STA 87+81.23	VAR			1,026.15	2.05	
STA 7+18.82	TO	STA 13+43.26	VAR			2,394.36	4.79	
STA 13+43.26	TO	STA 15+31.02	VAR			1,592.09	3.18	***
STA 15+31.02	TO	STA 17+42.49	VAR			859.79	1.72	
STA 17+42.49	TO	STA 26+00.00	VAR			5,473.81	10.95	****
STA 26+00.00	TO	STA 27+47.00	28 TO 30			473.67	0.95	
STA 27+47.00	TO	STA 28+80.00	44			650.22	1.30	
STA 28+80.00	TO	STA 41+98.04 BK	24			3,514.77	7.03	
STA 42+39.60 AH	TO	STA 58+66.00 BK	24			4,337.07	8.67	
STA 58+70.03 AH	TO	STA 58+79.00	24			23.92	0.05	
STA 58+79.00	TO	STA 60+81.00	30			673.33	1.35	
STA 60+81.00	TO	STA 100+89.78	24			10,690.08	21.38	
STA 100+89.78	TO	STA 102+35.45	24	4	4	517.94	1.04	
STA 102+35.45	TO	STA 107+29.75	26 TO 36	4	4	2,141.97	4.28	
STA 107+29.75	TO	STA 110+72.28	36	4	4	1,674.59	3.35	
STA 110+72.28	TO	STA 113+67.47	36 TO 26	4	4	1,279.16	2.56	
STA 113+67.47	TO	STA 119+82.61	24	4	4	2,187.16	4.37	
STA 119+82.61	TO	STA 124+54.86	26 TO 36	4	4	2,046.42	4.09	
STA 124+54.86	TO	STA 129+69.26	36	4	4	2,514.84	5.03	
STA 129+69.26	TO	STA 137+17.09	36 TO 26	4	4	3,240.60	6.48	
STA 137+17.09	TO	STA 154+00.00	24			4,487.76	8.98	
STA 174+00.00	TO	STA 206+47.00	24			8,658.67	17.32	
CONTINUED		CONTINUED	CONTINUED			CONTINUED	CONTINUED	

AGGREGATE (PRIME COAT)

LOCATION			PAVEMENT WIDTH (FOOT)	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)	QUANTITY (TONS)
SIDE STREETS							
Knute Rockne Road	LT	(ADD	VAR			208.13	0.42
Sportsman Drive	LT	(ADD	VAR			81.92	0.16
Hawley Street	RT	(ADD	VAR			102.62	0.21
Haner Street	RT	(ADD	VAR			125.13	0.25
LincolnStreet	LT	(ADD	VAR			82.47	0.16
Maxwell Street	RT	(ADD	VAR			95.53	0.19
Taft Street	RT	(ADD	VAR			89.02	0.18
Bidwell Street	LT	(ADD	VAR			70.78	0.14
West Bryant Street	RT	(ADD	VAR			87.99	0.18
Wilson Street	RT	(ADD	VAR			53.73	0.11
John Street	RT	(ADD	VAR			33.70	0.07
Washington Street	LT	(ADD	VAR			286.62	0.57
Washington Street	RT	(ADD	VAR			88.75	0.18
Main Street	LT	(ADD	VAR			218.28	0.44
Main Street	RT	(ADD	VAR			204.45	0.41
Walnut Street	LT	(ADD	VAR			42.18	0.08
Walnut Street	RT	(ADD	VAR			42.85	0.09
Cherokee Street	LT	(ADD	VAR			33.47	0.07
Cherokee Street	RT	(ADD	VAR			33.47	0.07
Cheyenne Street	RT	(ADD	VAR			87.76	0.18
Shawnee Street	LT	(ADD	VAR			89.53	0.18
Shawnee Street	RT	(ADD	VAR			48.73	0.10
Chestnut Street	RT	(ADD	VAR			50.89	0.10
Long Street	LT	(ADD	VAR			83.27	0.17
Long Street	RT	(ADD	VAR			58.32	0.12
Paw Paw Street	RT	(ADD	VAR			45.10	0.09
Lincoln Trail	LT	(ADD	VAR			2,572.53	5.15
Pershing Road	LT	(ADD				83.46	0.17
Pershing Road	RT	(ADD				82.19	0.16
STA 110+00.00	LT	(ADD		4	4	425.21	0.85
STA 128+10.00	LT	(ADD		4	4	436.34	0.87
STA 128+10.00	RT	(ADD		4	4	435.08	0.87
Velma Road	LT	(ADD				91.58	0.18
Velma Road	RT	(ADD				87.64	0.18
ENTRANCES							
STA 571+01.26	LT	(ADD	VAR			194.18	0.39
STA 573+69.00	LT	(ADD	VAR			265.22	0.53
STA 40+00.00	RT	(ADD				60.90	0.12
STA 40+10.00	LT	(ADD				49.97	0.10
STA 80+00.00	RT	(ADD				72.62	0.15
STA 80+15.00	LT	(ADD				29.96	0.06
STA 136+50.00	LT	(ADD				62.17	0.12
STA 139+50.00	LT	(ADD				49.07	0.10
TOTAL							230.54

* CHEYNEY INTERSECTION

** WEBSTER/PARK INTERSECTION

*** McADAM INTESECTION

**** MAIN CROSS/LINCOLN TRAIL. INT.

⚠ Rev. Sheet 2-22-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 75 (IL 29)
SECTION D 6 RESURFACING 2007
CHRISTIAN COUNTY

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 2/21/2007
FILE NAME = c:\pw_pwin\d0564683\schedules.dgn
PLOT SCALE = 185.6924 ' / IN.
USER NAME = loughlsrvl