

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

#D 6 RESURFACING 2007

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	COLOR / DESCRIPTION	# OF LINES	LENGTH (FOOT)
IL-29 MAINLINE			
STA 520+72.00 TO STA 524+91.00	YELLOW / MEDIAN	4	1,676.0
STA 525+87.00 TO STA 528+10.00	YELLOW / MEDIAN	4	892.0
STA 528+10.00 TO STA 530+88.00	YELLOW / MEDIAN	2	556.0
STA 531+91.00 TO STA 552+40.00	YELLOW / LTLC	2	4,098.0
STA 531+91.00 TO STA 552+40.00	YELLOW / LTLC SKIP DASHES	2	1,040.0
STA 552+40.00 TO STA 553+95.00	YELLOW / MEDIAN	4	620.0
STA 553+95.00 TO STA 556+07.00	YELLOW / MEDIAN	2	424.0
STA 556+93.00 TO STA 564+39.00	YELLOW / MEDIAN	2	1,492.0
STA 564+89.00 TO STA 568+00.00	YELLOW / MEDIAN	2	622.0
STA 568+30.00 TO STA 573+47.00	YELLOW / MEDIAN	2	1,034.0
STA 573+92.00 TO STA 578+14.00	YELLOW / MEDIAN	2	844.0
STA 579+13.00 TO STA 581+77.00	YELLOW / MEDIAN	2	528.0
STA 582+64.00 TO STA 583+24.00	YELLOW / MEDIAN	2	120.0
STA 583+12.00 TO STA 583+24.00	WHITE/ 2' SKIP DASH	1	12.0
STA 47+07.92 TO STA 48+24.00	WHITE/ 2' SKIP DASH	1	116.0
STA 47+07.92 TO STA 49+80.00	YELLOW / CL	2	544.0
STA 50+03.00 TO STA 52+97.00	YELLOW / CL	2	588.0
STA 50+25.00 TO STA 51+97.00	WHITE / EDGE	2	344.0
STA 53+60.00 TO STA 54+25.00	YELLOW / CL	2	130.0
STA 54+25.00 TO STA 56+47.00	YELLOW / MEDIAN	4	888.0
STA 56+47.00 TO STA 59+46.00	YELLOW / CL	2	598.0
STA 59+46.00 TO STA 61+64.00	YELLOW / MEDIAN	4	872.0
STA 61+64.00 TO STA 62+36.00	YELLOW / CL	2	144.0
STA 53+60.00 TO STA 62+36.00	WHITE / EDGE	2	1,752.0
STA 63+00.00 TO STA 63+70.00	YELLOW / CL	2	140.0
STA 63+70.00 TO STA 65+96.00	YELLOW / MEDIAN	4	904.0
STA 63+00.00 TO STA 69+00.00	WHITE / EDGE	2	1,200.0
STA 66+37.00 TO STA 69+00.00	YELLOW / CL	2	526.0
STA 69+53.00 TO STA 72+54.00	YELLOW / CL	2	602.0
STA 69+53.00 TO STA 76+04.00	WHITE / EDGE	2	1,302.0
STA 72+92.00 TO STA 76+04.00	YELLOW / CL	2	624.0
STA 76+46.00 TO STA 79+54.00	YELLOW / CL	2	616.0
STA 76+46.00 TO STA 87+81.23	WHITE / EDGE	2	2,270.0
STA 79+92.00 TO STA 87+81.23	YELLOW / CL	2	1,578.0
STA 7+18.82 TO STA 14+08.00	YELLOW / MEDIAN	2	1,378.0
STA 14+38.00 TO STA 14+38.00	MEDIAN / McADAM	2	164.1
STA 14+70.00 TO STA 18+24.00	YELLOW / MEDIAN	2	708.0
STA 19+88.00 TO STA 25+46.00	YELLOW / MEDIAN	2	1,116.0
STA 25+46.00 TO STA 27+47.00	YELLOW / NB NPZ	1	201.0
STA 25+46.00 TO STA 27+47.00	YELLOW SKIP DASH / CL	1	60.0
STA 27+47.00 TO STA 28+80.00	YELLOW SKIP DASH / CL BRIDGE	1	40.0
STA 28+80.00 TO STA 41+98.04 BK	YELLOW SKIP DASH / CL	1	330.0
STA 42+39.60 AH TO STA 58+66.00 BK	YELLOW SKIP DASH / CL	1	410.0
STA 58+70.03 AH TO STA 58+79.00	YELLOW SKIP DASH / CL	1	10.0
STA 58+79.00 TO STA 60+81.00	YELLOW SKIP DASH / CL BRIDGE	1	60.0
STA 60+81.00 TO STA 87+50.00	YELLOW SKIP DASH / CL	1	670.0
STA 77+00.00 TO STA 87+50.00	YELLOW SB NPZ	1	1,050.0
STA 87+50.00 TO STA 101+88.00	YELLOW NB & SB NPZ	2	2,876.0
CONTINUED	CONTINUED	CONTINUED	CONTINUED

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	COLOR / DESCRIPTION	# OF LINES	LENGTH (FOOT)
STA 101+88.00 TO STA 107+30.00	YELLOW / MEDIAN	4	2,168.0
STA 107+30.00 TO STA 109+76.00	YELLOW / MEDIAN	2	492.0
STA 109+99.00 TO STA 109+99.00	MEDIAN / KENNEDY ROAD	2	115.0
STA 110+20.00 TO STA 113+67.00	YELLOW / MEDIAN	4	1,388.0
STA 113+67.00 TO STA 119+83.00	YELLOW / MEDIAN	2	1,232.0
STA 119+83.00 TO STA 126+32.00	YELLOW / MEDIAN	4	2,596.0
STA 126+32.00 TO STA 127+47.00	YELLOW / MEDIAN	2	230.0
STA 128+00.00 TO STA 128+00.00	MEDIAN / N. LAKE ROAD	2	104.0
STA 128+00.00 TO STA 128+00.00	MEDIAN / S. LAKE ROAD	2	76.0
STA 128+54.00 TO STA 129+69.00	YELLOW / MEDIAN	2	230.0
STA 129+69.00 TO STA 136+19.00	YELLOW / MEDIAN	4	2,600.0
STA 136+19.00 TO STA 154+00.00	YELLOW SKIP DASH / CL	1	450.0
STA 174+00.00 TO STA 205+09.00	YELLOW SKIP DASH / CL	1	780.0
STA 205+09.00 TO STA 206+47.00	YELLOW SKIP DASH / CL	1	138.0
STA 7+18.82 TO STA 13+51.00	EDGE / WHITE	2	1,264.0
STA 13+51.00 TO STA 15+31.00	EDGE / WHITE	1	180.0
STA 13+51.00 TO STA 14+08.00	EDGE McADAM/ WHITE	1	121.7
STA 14+42.00 TO STA 15+31.00	EDGE McADAM/ WHITE	1	150.9
STA 15+31.00 TO STA 17+83.59	EDGE / WHITE	2	505.0
STA 20+23.13 TO STA 27+47.00	EDGE / WHITE	2	1,448.0
STA 27+47.00 TO STA 28+80.00	EDGE BRIDGE / WHITE	2	266.0
STA 28+80.00 TO STA 31+19.00	EDGE / WHITE	2	478.0
STA 32+05.00 TO STA 41+98.04 BK	EDGE / WHITE	2	1,986.0
STA 42+39.60 AH TO STA 58+66.00 BK	EDGE / WHITE	2	3,253.0
STA 58+70.03 AH TO STA 58+79.00	EDGE / WHITE	2	18.0
STA 58+79.00 TO STA 60+81.00	EDGE BRIDGE / WHITE	2	404.0
STA 60+81.00 TO STA 109+09.00	EDGE / WHITE	2	9,656.0
STA 109+09.00 TO STA 110+52.00	EDGE KENNEDY ROAD/ WHITE	2	488.0
STA 109+09.00 TO STA 110+52.00	EDGE / WHITE	1	143.0
STA 110+52.00 TO STA 127+23.80	EDGE / WHITE	2	3,344.0
STA 127+23.80 TO STA 129+02.45	EDGE N. LAKE ROAD/ WHITE	2	236.5
STA 127+23.80 TO STA 129+02.45	EDGE S. LAKE ROAD/ WHITE	2	245.8
STA 129+02.00 TO STA 154+00.00	EDGE / WHITE	2	4,996.0
STA 174+00.00 TO STA 204+25.00	EDGE / WHITE	2	6,050.0
STA 205+09.00 TO STA 206+47.00	EDGE / WHITE	2	276.0
CHENEY			
STA 8+55.00 TO STA 9+42.00	YELLOW / MEDIAN	2	174.0
STA 10+50.00 TO STA 11+25.00	YELLOW / MEDIAN	2	150.0
SOUTH WEBSTER			
STA 114+26.00 TO STA 115+06.00	YELLOW / MEDIAN	2	160.0
WEST PARK			
STA 8+70.00 TO STA 9+53.00	YELLOW / MEDIAN	2	166.0
MAIN CROSS			
STA 9+78.00 TO STA 11+47.00	EDGE / WHITE	2	338.0
STA 9+78.00 TO STA 10+85.00	YELLOW / MEDIAN	2	214.0
LINCOLN TRAIL			
STA 11+07.00 TO STA 18+93.00	EDGE / WHITE	2	1,572.0
STA 11+76.00 TO STA 17+45.00	YELLOW / MEDIAN	2	1,140.0
STA 17+85.00 TO STA 18+93.00	YELLOW / MEDIAN	2	216.0
STA 15+00.00 TO STA 16+61.00	WHITE / 2' SKIP DASH	1	164.0
TOTAL			91,171.9

PLOT DATE : 2/21/2007
 FILE NAME : I:\PROJECTS\72826\thermo.dgn
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : laughton

Rev. Sheet 2-22-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 75 (IL 29)

SECTION D 6 RESURFACING 2007

CHRISTIAN COUNTY

SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY: