

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

*D 6 RESURFACING 2007

HMA SURFACE REMOVAL - BUTT JOINT

LOCATION	LENGTH (FOOT)	PAVEMENT WIDTH (FOOT)	AREA (SQ YD)
I-29 MAINLINE			
STA 28+80.00 TO STA 29+10.00	30	24	80.00
STA 206+17.00 TO STA 206+47.00	30	24	80.00
STA 153+70.00 TO STA 154+00.00	30	24	80.00
STA 174+00.00 TO STA 174+30.00	30	24	80.00
SIDE STREETS			
PERSHING RD LT SR	VAR	VAR	83.46
PERSHING RD RT SR	VAR	VAR	82.19
KENNEDY LT SR	VAR	VAR	425.21
LAKE LT SR	VAR	VAR	436.34
LAKE RT SR	VAR	VAR	435.08
VELMA RD LT SR	VAR	VAR	91.58
VELMA RD RT SR	VAR	VAR	87.64
ENTRANCES			
STA 40+00.00 RT PE	VAR	VAR	60.90
STA 40+10.00 LT PE	VAR	VAR	49.97
STA 80+00.00 RT PE	VAR	VAR	72.62
STA 80+15.00 LT PE	VAR	VAR	29.96
STA 136+50.00 LT PE	VAR	VAR	62.17
STA 139+50.00 LT PE	VAR	VAR	49.07
TOTAL			2,286.19

SHOULDER RUMBLE STRIPS

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	LENGTH (FOOT)
I-29 MAINLINE			
STA 28+80.00 TO STA 31+19.00	3	3	478.00
STA 32+05.00 TO STA 39+52.00	0	3	747.00
STA 32+05.00 TO STA 39+86.00	3	0	781.00
STA 40+28.00 TO STA 41+98.04 BK	0	3	170.04
STA 40+50.00 TO STA 41+98.04 BK	3	0	148.04
STA 42+39.60 AH TO STA 58+66.00 BK	3	3	3,252.80
STA 58+70.03 AH TO STA 58+79.00	3	3	17.94
STA 60+81.00 TO STA 79+60.00	0	3	1,879.00
STA 60+81.00 TO STA 80+05.00	3	0	1,924.00
STA 80+48.00 TO STA 127+33.00	0	3	4,685.00
STA 80+45.00 TO STA 109+09.00	3	0	2,864.00
STA 110+51.00 TO STA 127+33.00	3	0	1,682.00
STA 128+92.00 TO STA 136+21.00	3	0	729.00
STA 128+92.00 TO STA 154+00.00	0	3	2,508.00
STA 174+00.00 TO STA 204+26.00	0	3	3,026.00
STA 137+00.00 TO STA 139+21.00	3	0	221.00
STA 139+75.00 TO STA 154+00.00	3	0	1,425.00
STA 174+00.00 TO STA 204+16.00	3	0	3,016.00
STA 205+27.00 TO STA 206+47.00	0	3	120.00
STA 205+09.00 TO STA 206+47.00	3	0	138.00
TOTAL			29,811.82

HOT-MIX ASPHALT SHOULDERS

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	TONS
I-29 MAINLINE			
STA 100+89.78 TO STA 109+09.00	4	0	45.88
STA 100+89.78 TO STA 127+33.00	0	4	148.02
STA 128+92.00 TO STA 137+17.09	0	4	46.21
STA 110+51.00 TO STA 127+33.00	4	0	94.19
STA 128+92.00 TO STA 136+21.00	4	0	40.82
STA 137+00.00 TO STA 137+17.09	4	0	0.96
TOTAL			376.08

INSERTION CULVERT LINER (SPECIAL)

LOCATION	LENGTH FOOT
LT STA 47+04 TO LT STA 49+61	258
TOTAL	258

MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME,

OPEN LID

LOCATION	EACH
RT STA 45+03 (69' RT)	1
TOTAL	1

MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME,

CLOSED LID

LOCATION	EACH
LT STA 47+04 (23' LT)	1
TOTAL	1

STORM SEWERS JACKED IN PLACE, CLASS A 36"

LOCATION	LENGTH FOOT
LT STA 47+04 TO RT STA 45+03	221
TOTAL	221

SEEDING, CLASS 2 (SPECIAL)

LOCATION	LENGTH FOOT	WIDTH FOOT	AREA SQ FT	AREA ACRE
RT STA 45+03	100	50	5000	0.11
LT STA 47+04	100	45	4500	0.10
TOTAL				0.21

TEMPORARY SHEET PILING

LOCATION	LENGTH FOOT	DEPTH FOOT	AREA SQ FT
RT STA 46+54 TO 47+54	100	40	4000
TOTAL			4000

** - CONTRACTOR SHALL DESIGN SHEET PILING

PLOT DATE = 2/21/2007
 FILE NAME = I:\AS-4833\sheet\as.dgn
 PLOT SCALE = 1/8"=1'-0" / 30"
 USER NAME = laughton

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY
 SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY:

Rev. Sheet 2-22-07