

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75		CHRISTIAN	97	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"

LOCATION	DIRECTION	DESCRIPTION	LENGTH (FOOT)
IL-29 MAINLINE			
STA 524+88.00	EB	STOP BAR	11.5
STA 525+10.00	EB	STOP BAR	12.0
STA 525+32.44	EB	STOP BAR	14.0
STA 525+74.00	WB	STOP BAR	14.3
STA 525+90.01	WB	STOP BAR	12.0
STA 556+07.00	EB	STOP BAR	24.2
STA 556+93.00	WB	STOP BAR	29.4
STA 578+14.00	S	STOP BAR	23.8
STA 578+10.33	SW	STOP BAR	18.8
STA 579+12.00	WB	STOP BAR	23.8
STA 579+32.32	NW	STOP BAR	18.2
STA 52+97.00	EB	STOP BAR	23.0
STA 53+60.00	WB	STOP BAR	23.0
STA 62+36.00	EB	STOP BAR	23.0
STA 63+00.00	WB	STOP BAR	23.0
STA 18+22.00	WB	STOP BAR	27.0
STA 19+97.00	WB	STOP BAR	27.0
CHENEY ST.			
STA 524+76.79	TO STA 524+95.19	S	STOP BAR 20.0
STA 525+03.70	TO STA 525+16.31	S	STOP BAR 13.8
STA 525+63.71	TO STA 525+79.37	N	STOP BAR 18.6
STA 526+15.33	TO STA 526+32.28	NE	STOP BAR 22.0
PARK			
STA 9+51.00	E	STOP BAR	12.0
STA 9+66.00	E	STOP BAR	12.0
STA 9+47.00	SE	STOP BAR	19.9
NORTH WEBSTER			
STA 115+05.00	N	STOP BAR	12.0
STA 115+10.00	N	STOP BAR	12.0
STA 114+94.00	NE	STOP BAR	17.8
N. MAIN ST.	S	STOP BAR	20.0
S. MAIN ST.	N	STOP BAR	17.0
MCADAM	S	STOP BAR	16.0
MCADAM	S	STOP BAR	26.0
MAIN CROSS			
STA 10+85.00	N	STOP BAR	12.0
STA 11+04.00	N	STOP BAR	16.0
LINCOLN TRAIL			
STA 11+67.00	S	STOP BAR	16.0
STA 11+87.00	S	STOP BAR	12.0
KENNEDY			
N. LAKE		STOP BAR	18.3
S. LAKE		STOP BAR	13.2
TOTAL			722.1

HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"

LOCATION	BRIDGE WIDTH (FOOT)	AREA (SQ YD)	
I-29 MAINLINE			
STA 27+47.00	TO STA 28+80.00	44	650.22
STA 58+79.00	TO STA 60+81.00	30	673.33
TOTAL			1,323.55

HMA SHOULDERS 8"

LOCATION	LT SHLD WIDTH	RT SHLD WIDTH	AREA (SQ YD)	
I-29 MAINLINE				
STA 28+80.00	TO STA 31+19.00	3	3	159.33
STA 32+05.00	TO STA 39+52.00	0	3	249.00
STA 32+05.00	TO STA 39+86.00	3	0	260.33
STA 40+28.00	TO STA 41+98.04 BK	0	3	56.68
STA 40+50.00	TO STA 41+98.04 BK	3	0	49.35
STA 42+39.60 AH	TO STA 58+66.00 BK	3	3	1,084.27
STA 58+70.03 AH	TO STA 58+79.00	3	3	5.98
STA 60+81.00	TO STA 79+60.00	0	3	626.33
STA 60+81.00	TO STA 80+05.00	3	0	641.33
STA 80+48.00	TO STA 100+89.78	0	3	680.59
STA 80+45.00	TO STA 100+89.78	3	0	681.59
STA 137+17.09	TO STA 154+00.00	0	3	560.97
STA 174+00.00	TO STA 204+26.00	0	3	1,008.67
STA 137+17.09	TO STA 139+21.00	3	0	67.97
STA 139+75.00	TO STA 154+00.00	3	0	475.00
STA 174+00.00	TO STA 204+16.00	3	0	1,005.33
STA 205+27.00	TO STA 206+47.00	0	3	40.00
STA 205+09.00	TO STA 206+47.00	3	0	46.00
TOTAL				7,698.72

VALVE VAULTS TO BE ADJUSTED

LOCATION	EACH
IL 29 MAINLINE	
STA 526+40.00	RT 1
STA 543+51.00	RT 1
STA 543+55.00	RT 1
STA 543+90.00	RT 1
STA 543+95.00	RT 1
STA 546+91.00	RT 1
STA 551+22.00	RT 1
STA 551+30.00	RT 1
STA 564+55.00	RT 1
STA 564+55.00	RT 1
STA 564+59.00	RT 1
STA 577+85.00	RT 1
STA 115+02.00	LT 1
STA 582+62.00	RT 1
STA 49+49.00	RT 1
STA 50+52.00	RT 1
STA 53+11.00	RT 1
STA 53+56.00	RT 1
STA 62+48.00	RT 1
STA 69+61.00	RT 1
STA 79+60.00	RT 1
STA 79+87.00	RT 1
TOTAL	22

MANHOLES TO BE ADJUSTED

LOCATION	EACH
IL 29 MAINLINE	
STA 539+77.00	LT 1
STA 571+18.00	LT 1
STA 573+14.00	LT 1
STA 573+95.00	LT 1
STA 574+07.00	CL 1
STA 577+53.00	CL 1
STA 115+00.00	1
STA 53+08.00	LT 1
STA 53+16.00	LT 1
STA 53+45.00	RT 1
STA 69+32.00	RT 1
STA 11+91.00	MEDIAN 1
STA 127+87.00	RT 1
TOTAL	13

Rev. Sheet 2-22-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAP 75 (IL 29)
 SECTION D 6 RESURFACING 2007
 CHRISTIAN COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE