

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75		CHRISTIAN	97	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

* D 6 RESURFACING 2007

LOCATION OF WORK			80% FED. 20% STATE	IL 29: CHENEY TO IL 48	IL 29: IL 48 TO KENNEDY, LAKE TO VELMA RD	IL 29: KENNEDY TO LAKE	SN 011-0010: IL 29 OVER IL 48	SN 011-0011: IL 29 OVER FLAT BRANCH	STORM SEWER IMPROVEMENTS
				URBAN	RURAL	RURAL	RURAL	RURAL	URBAN
SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000	SFTY-2A	SFTY-2A	Y007
20200500	EARTH EXCAVATION (WIDENING)	CU YD	2,000		2,000				
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.21						0.21
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	23.7	14.3	6.4	0.3	0.3	
40600300	AGGREGATE (PRIME COAT)	TON	236	124	76	34	1	1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2,076		1,556	520			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	2,243		946	1,297			
40600990	TEMPORARY RAMP	SQ YD	1,057	723	291	43			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,872	6,626	3,112	1,040	46.4	47.6	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	520	345	66	109			
44000152	HOT-MIX ASPHALT SURFACE REMOVAL 3/4"	SQ YD	1327				660	677	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	62,429	62,429					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	52,462		36,860	15,602			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	625	625					
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	1,395	815	580				
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	640	325	315				
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	675	360	315				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,716	119	913	684			
48203029	HOT-MIX ASPHALT SHOULDERS 8"	SQ YD	8,984		8,984				
48203100	HOT-MIX ASPHALT SHOULDERS	TON	376			376			
51205200	TEMPORARY SHEET PILING	SQ FT	4,000						4,000
552A1300	STORM SEWERS JACKED IN PLACE, CLASS A 36"	FOOT	221						221
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1						1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1						1
60255500	MANHOLES TO BE ADJUSTED	EACH	13	12		1			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	22	22					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	625	625					
63300575	REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	6,100			1,388	4,712		
64200105	SHOULDER RUMBLE STRIPS	FOOT	33,669		19,228	14,441			

PLOT DATE = 12/28/2006
FILE NAME = c:\pwork\res\72826\803\road.dgn
PLOT SCALE = 42.3529' / IN.
USER NAME = laughlinr1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 75 (IL 29)
SECTION D 6 RESURFACING 2007
CHRISTIAN COUNTY
SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____

Rev.

Rev.