

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	*	CHRISTIAN	97	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

\* D 6 RESURFACING 2007

LOCATION OF WORK	90% FED. 10% STATE	IL 29: CHENEY TO IL 48	IL 29: IL 48 TO KENNEDY, LAKE TO VELMA RD	IL 29: KENNEDY TO LAKE	SN 011-0010: IL 29 OVER IL 48	SN 011-0011: IL 29 OVER FLAT BRANCH	STORM SEWER IMPROVEMENTS	SUMMARY OF QUANTITIES		
								URBAN	RURAL	URBAN
CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE									
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000	SFTY-2A	SFTY-2A	Y007	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5						
67100100	MOBILIZATION	L SUM	1	0.3	0.3	0.2	0.1	0.1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5					
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		0.7	0.3				
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5					
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1						1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.4	0.6					
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1						
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1						
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
70103815	TRAFFIC CONTRAL SURVEILLANCE	CAL DA	8		8					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,825	6,495	3,820	510				
70300200	TEMPORARY PAVEMENT MARKING	FOOT	99,767	45,382	34,963	19,422				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1,358	696	500	162				
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	93,190	38,805	34,657	18,958	306.0	464.0		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	477			477				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,507	1,507						
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,397	751		646				
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	1,389	1,280		109				
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	940	940						
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	5,637	5,637						
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	570	514		56				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,154	725	178	251				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,154	725	178	251				
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2,937	2,937						
X5430100	INSERTION CULVERT LINER (SPECIAL)	FOOT	258						258	
XX005399	TEMPORARY SOIL RETENTION AND DEWATERING SYSTEM	L SUM	1						1	
Z0012500	CONCRETE CURB REPAIR	FOOT	775	775						
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1						1	
X0325675	TEMPORARY RUBBER RAMPS FOR DRAINAGE AND UTILITY CASTINGS	EACH	35	34		1				
X0321744	SILICONE JOINT SEALER 2"	FOOT	78			48		30		
X0322932	SILICONE JOINT SEALER 1/2"	FOOT	78			48		30		
X0320887	POLYMER CONCRETE	CU FT	15			9.2		5.8		

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAP 75 (IL 29)  
SECTION D 6 RESURFACING 2007  
CHRISTIAN COUNTY

SCALE: VERT.      DRAWN BY  
          HORIZ.      CHECKED BY  
DATE

Rev.